VAV BOX WITH HOT WATER REHEAT SCHEDULE

IDENTITY DATA					AIRFLOW DATA						REHEAT COIL DATA									
MARK	MANUFACTURER	MODEL	ROOMS SERVED	INLET DIAMETER	COOLING MAX AIRFLOW (CFM)	HEATING MAX AIRFLOW (CFM)	OCCUPIED MINIMUM AIRFLOW (CFM)	UNOCCUPIED MINIMUM AIRFLOW (CFM)	MAX N.C. DISCHARGED	MAX N.C. RADIATED	CAPACITY (BTUH)	EAT (°F)	LAT (°F)	APD (IN W.G.)	FLOW (GPM)	EWT (°F)	LWT (°F)	WPD (FT-WG)	ROWS	NOTES
1-01	PRICE	SDV	CORRIDOR B (BC118)	10"	700	700	700	250	0	20	27,000	55	90.6	1	3	140.0	121.8	0	0	1-5
1-02	PRICE	SDV	DIGITAL LAB (B119)	8"	400	400	400	200	0	20	17,400	55	94.9	1	2.5	140.0	126	0	0	1-5
1-03	PRICE	SDV	CLASS (B120)	14"	1,475	1,475	800	350	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-04	PRICE	SDV	SCIENCE LAB (B117)	12"	1,000	1,000	0	0	0	20	38,600	55	90.6	1	4.5	140.0	122.6	0	0	1-5
1-05	PRICE	SDV	CLASS (B118)	14"	1,475	1,475	800	350	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-06	PRICE	SDV	COMMONS B (BC117)	8"	500	500	500	200	0	20	19,500	55	90.8	1	2.5	140.0	124.3	0	0	1-5
1-07	PRICE	SDV	COMMONS B (BC117)	12"	1,000	1,000	1,000	350	0	20	43,800	55	95.4	1	5	140.0	122.2	0	0	1-5
1-08	PRICE	SDV	CLASS (B114)	14"	1,475	1,475	800	350	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-09	PRICE	SDV	COMMONS B (BC117)	12"	1,200	1,200	1,200	350	0	20	46,700	55	90.9	1	4.5	140.0	119	0	0	1-5
1-10	PRICE	SDV	RESTROOMS AND CORRIDOR (LVL 1)	16"	1,980	1,980	800	800	0	20	56,700	55	90.5	1	4.5	140.0	114.4	0	0	1-5
1-11	PRICE	SDV	CLASS (B112)	14"	1,475	1,475	800	350	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-12	PRICE	SDV	CLASS (B110)	14"	1,475	1,475	800	350	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-13	PRICE	SDV	SMALL GROUP COLLAB (B109)	10"	700	700	500	250	0	20	31,000	55	95.7	1	3.5	140.0	122.1	0	0	1-5
1-14	PRICE	SDV	T. STAFF RR's (LVL 1)	8"	550	550	550	0	0	20	21,400	55	90.8	1	3.5	140.0	127.6	0	0	1-5
1-15	PRICE	SDV	SMALL GROUP COLLAB (B108)	8"	400	400	250	175	0	20	15,900	55	91.4	1	1.5	140.0	118.7	0	0	1-5
1-16	PRICE	SDV	TEACHER COLLAB (B129)	12"	1,440	1,440	0	0	0	20	54,200	55	95	1	4.52	140.0	115.7	0	0	1-5
1-17	PRICE	SDV	CLASS (B106)	14"	1,475	1,475	800	350	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-18	PRICE	SDV	CLASS (B104)	14"	1,475	1,475	0	0	0	20	56,200	55	90.2	1	4	140.0	111.5	0	0	1-5
1-19	PRICE	SDV	SMALL GROUP COLLAB (B103)	12"	850	850	0	0	0	20	37,700	55	95.9	1	3.5	140.0	118.2	0	0	1-5
1-20	PRICE	SDV	SMALL GROUP COLLAB (B131)	8"	800	800	450	350	0	20	21,800	55	95	1	2.5	140.0	122.4	0	0	1-5
1-21	PRICE	SDV	CLASS (B102)	14"	1,475	1,475	800	350	0	20	63,900	55	95	1	6.65	140.0	120.5	0	0	1-5
1-22	PRICE	SDV	CORRIDOR B (BC101)	10"	700	350	350	250	0	20	27,100	55	90.7	1	2	140.0	112.5	0	0	1-5
1-23	PRICE	SDV	CORRIDOR B (BC101)	12"	800	800	400	250	0	20	35,300	55	95.7	1	3	140.0	116.1	0	0	1-5
1-24	PRICE	SDV	FRESHMAN ASST. PRIN. (B100C)	10"	925	450	450	250	0	20	18,700	55	93.1	1	1.5	140.0	114.8	0	0	1-5
1-25	PRICE	SDV	GUID WAIT (B100J)	8"	525	250	200	200	0	20	11,400	55	96.8	1	1	140.0	117	0	0	1-5
1-26	PRICE	SDV	OFFICE (B101J)	12"	800	400	400	250	0	20	16,700	55	93.3	1	1	140.0	106.3	0	0	1-5
1-27	PRICE	SDV	CONF (B101G)	6"	250	125	125	75	0	20	4,900	55	90	1	0.25	140.0	101.6	0	0	1-5
1-28	PRICE	SDV	OFFICE (B101E)	6"	300	200	150	125	0	20	7,800	55	90.4	1	0.5	140.0	108.8	0	0	1-5
1-29	PRICE	SDV	INTERACTIVE SPACE (B101C)	10"	700	700	250	250	0	20	31,000	55	95.7	1	3.5	140.0	122.1	0	0	1-5
1-30	PRICE	SDV	PRINCIPAL (B101A)	14"	1,475	1,200	800	350	0	20	53,100	55	95.8	1	4.5	140.0	116	0	0	1-5
1-31	PRICE	SDV	CORRIDOR (BC218)	10"	725	725	725	250	0	20	27,500	55	90	1	2	140.0	112.1	0	0	1-5
1-32	PRICE	SDV	BREAKOUT (B221)	8"	400	400	0	0	0	20	15,900	55	91.4	1	1.5	140.0	118.7	0	0	1-5
1-33	PRICE	SDV	SCIENCE LAB (B217)	12"	1,000	1,000	0	0	0	20	38,600	55	90.6	1	4.5	140.0	122.6	0	0	1-5
1-34	PRICE	SDV	COMMONS B (BC217)	12"	1,000	1,000	0	0	0	20	43,800	55	95.4	1	5	140.0	122.2	0	0	1-5
1-35	PRICE	SDV	COMMONS B (BC217)	12"	1,200	1,200	1,200	325	0	20	46,700	55	90.9	1	4.5	140.0	119	0	0	1-5
1-36	PRICE	SDV	RESTROOMS AND CORRIDOR (LVL 2)	14"	1,800	1,800	1,800	425	0	20	69,800	55	90.8	1	5	140.0	111.7	0	0	1-5
1-37	PRICE	SDV	SMALL GROUP COLLAB (B209)	10"	700	700	400	250	0	20	31,000	55	95.7	1	3.5	140.0	122.1	0	0	1-5
1-38	PRICE	SDV	T. STAFF RR's (LVL 2)	8"	550	550	300	200	0	20	24,000	55	95.2	1	3.5	140.0	126.1	0	0	1-5
1-39	PRICE	SDV	SMALL GROUP COLLAB (B208)	8"	500	500	300	175	0	20	21,800	55	95	1	2.5	140.0	122.4	0	0	1-5
1-40	PRICE	SDV	TEACHER COLLAB (B229)	12"	1,440	1,440	0	0	0	20	54,200	55	95	1	4.5	140.0	115.6	0	0	1-5
1-41	PRICE	SDV	SMALL GROUP COLLAB (B203)	12"	1,100	725	725	375	0	20	32,100	55	95.8	1	2.5	140.0	114	0	0	1-5
1-42	PRICE	SDV	HELP DESK STORAGE (B231)	8"	800	800	0	0	0	20	21,800	55	95	1	2.5	140.0	122.4	0	0	1-5
1-43	PRICE	SDV	CORRIDOR (BC201)	12"	1,100	1,100	525	325	0	20	42,400	55	90.5	1	3.5	140.0	115.5	0	0	1-5
1-44	PRICE	SDV	ISS (B200)	8"	500	300	300	200	0	20	13,700	55	96.9	1	1	140.0	112.4	0	0	1-5
1-45	PRICE	SDV	ATTEND. DEAN (B200A)	8"	550	300	300	175	0	20	13,700	55	96.9	1	1	140.0	112.4	0	0	1-5
1-46	PRICE	SDV	ASST. PRIN. (B200C)	8"	600	400	300	175	0	20	17,500	55	95.3	1	1.5	140.0	116.4	0	0	1-5
1-47	PRICE	SDV	GUIDANCE HUB (B200P)	8"	400	275	275	175	0	20	12,000	55	94.9	1	1	140.0	115.9	0	0	1-5
1-48	PRICE	SDV	CONF (B200E)	8"	450	275	275	175	0	20	12,000	55	94.9	1	1	140.0	115.9	0	0	1-5
1-49	PRICE	SDV	GUID. RES. (B200M)	8"	450	300	275	175	0	20	12,500	55	93.2	1	1	140.0	114.8	0	0	1-5
1-50	PRICE	SDV	OFFICE (B200G)	8"	400	300	300	175	0	20	13,700	55	96.9	1	1	140.0	112.4	0	0	1-5
1-51	PRICE	SDV	OFFICE (B200J)	10"	825	500	500	250	0	20	23,300	55	97.9	1	2	140.0	116.4	0	0	1-5
1-52	PRICE	SDV	CONF (B200K)	10"	700	400	400	250	0	20	19,300	55	99.4	1	1.5	140.0	113.9	0	0	1-5
1-53	PRICE	SDV	CORRIDOR B (BC318)	10"	700	700	400	250	0	20	31,000	55	95.7	1	3.5	140.0	122.1	0	0	1-5
1-54	PRICE	SDV	DIGITAL LAB (B321)	8"	400	400	0	0	0	20	17,500	55	95.3	1	1.5	140.0	116.4	0	0	1-5
1-55	PRICE	SDV	SCIENCE LAB (B317)	12"	1,000	1,000	0	0	0	20	43,800	55	95.4	1	5	140.0	122.2	0	0	1-5
1-56	PRICE	SDV	COMMONS B (BC317)	12"	1,000	1,000	0	0	0	20	43,800	55	95.4	1	5	140.0	122.2	0	0	1-5
1-57	PRICE	SDV	COMMONS B (BC317)	14"	1,200	1,200	600	325	0	20	53,100	55	95.8	1	4.5	140.0	116	0	0	1-5
1-58	PRICE	SDV	RESTROOMS AND CORRIDOR (LVL 3)	14"	1,800	1,800	900	425	0	20	79,300	55	95.7	1	4.5	140.0	104.2	0	0	1-5
1-59	PRICE	SDV	SMALL GROUP COLLAB (B309)	10"	700	700	400	250	0	20	31,000	55	95.7	1	3.5	140.0	122.1	0	0	1-5
1-60	PRICE	SDV	T. STAFF RR's (LVL 3)	8"	400	400	250	175	0	20	17,500	55	95.3	1	1.5	140.0	116.4	0	0	1-5
1-61	PRICE	SDV	ASST. PRIN. (B300B)	12"	900	900	500	375	0	20	26,800	55	96.2	1	2.5	140.0	118.3	0	0	1-5
1-62	PRICE	SDV	SMALL GROUP COLLAB (B308)	8"	500	500	300	175	0	20	21,800	55	95	1	2.5	140.0	122.4	0	0	1-5
1-63	PRICE	SDV	TEACHER COLLAB (B329)	12"	1,300	1,300	0	0	0	20	54,200	55	95	1	4.5	140.0	115.6	0	0	1-5
1-64	PRICE	SDV	SMALL GROUP COLLAB (B303)	12"	1,100	1,100	500	325	0	20	47,700	55	95	1	3.5	140.0	112.4	0	0	1-5
1-65	PRICE	SDV	SMALL GROUP COLLAB (B331)	8"	800	800	0	0	0	20	21,800	55	95	1	2.5	140.0	122.4	0	0	1-5
1-66	PRICE	SDV	CORRIDOR (BC303)	12"	1,000	1,000	500	325	0	20	43,800	55	95.4	1	5	140.0	122.2	0	0	1-5
1-67	PRICE	SDV	MY ACHIEVEMENT CTR (B300J)	8"	425	425	275	175	0	20	19,300	55	96.7	1	2	140.0	120.5	0	0	1-5
1-68	PRICE	SDV	SMALL GROUP COLLAB (B300)	8"	500	500	300	175	0	20	21,800	55	95	1	2.5	140.0	122.4	0	0	1-5
1-69	PRICE	SDV	CONF (B300E)	6"	325	325	200	175	0	20	14,500	55	95.9	1	1.5	140.0	120.5	0	0	1-5
1-70	PRICE	SDV	OFFICE (B300D)	6"	300	300	250	175	0	20	19,800	55	95.5	1	2	140.0	120	0	0	1-5
1-71	PRICE	SDV	STAIRS B (BS102)	12"	1,025	950	0	0	0	20	0	55	95	1	0	140.0	100	0	0	1-5
1-72	PRICE	SDV	STAIRS B (BS203)	12"	950	850	0	0	0	20	0	55	95	1	0	140.0	100	0	0	1-5
1-73	PRICE	SDV	STAIRS B (BS303)	12"	950	850	0	0	0	20	0	55	95	1	0	140.0	100	0	0	1-5
1-74	PRICE	SDV	STAIRS B (BS126)	12"	1,000	900	0	0	0	20	0	55	90	1	0	140.0	100	0	0	1-5
1-75	PRICE	SDV	STAIRS B (BS226)	12"	1,000	900	0	0	0	20	0	55	90	1	0	140.0	100	0	0	1-5
1-76	PRICE	SDV	STAIRS B (BS326)	12"	1,000	900	0	0	0	20	0	55	90	1	0	140.0	100	0	0	1-5
2-01	PRICE	SDV	CORRIDOR A (AC101)	6"	350	200	200	200	0	20	7,800	55	90.4	1	0.5	140.0	108.8	0	0	1-5
2-02	PRICE	SDV	CLINIC (A102)	10"	670	600	600	250	0	20	23,000	55	90.3	1	2	140.0	116.7	0	0	1-5
2-03	PRICE	SDV	REG (A101K)	8"	550	300	300	200	0	20	12,500	55	93.2	1	1	140.0	114.8	0	0	1-5
2-04	PRICE	SDV	CONNECTING CORRIDOR	10"	600	600	600	200	0	20	26,800	55	96.2	1	2.5	140.0	118.3	0	0	1-5
2-05	PRICE	SDV	LOBBY A (AC100)	12"	900	900	900	300	0	20	39,900	55	95.9	1	4	140.0	119.8	0	0	1-5
2-06	PRICE	SDV	MAIL (A101E)	8"	500	250	250	200	0	20	11,400	55	96.8	1	1	140.0	117	0	0	1-5
2-07	PRICE	SDV	RECEPT (A101)	8"	525	300	300	200	0	20	13,700	55	96.9	1	1	140.0	112.4	0	0	1-5
2-08	PRICE	SDV	WAITING (A101A)	12"	1,000	1,000	500	350	0	20	43,800	55	95.4	1	5	140.0	122.2	0	0	1-5
2-09	PRICE	SDV	VEST A (AV101)	12"	1,250	1,250	500	350	0	20	47,500	55	90.1	1	4.5	140.0	118.6	0	0	1-5

VAV BOX SCHEDULE NOTES:

1. DDC CONTROLS WITH BACNET MS/TP INTERFACE ARE TO BE PROVIDED BY TEMPERATURE CONTROL CONTRACTOR. SHIPPED TO VAV BOX MANUFACTURER, AND FACTORY MOUNTED. CONTROLLER TO OPERATE AT MINIMUM VELOCITY PRESSURE SENSOR READING OF .004" W.C. FLOW PROBE TO HAVE AMPLIFICATION FACTOR GREATER THAN OR EQUAL TO 2. IN THE CASE THAT CONTROLLER'S MINIMUM BALANCEABLE AIRFLOW EXCEEDS SCHEDULED VALUE, MINIMUM AIRFLOW SETPOINT IS TO BE SET TO THAT AIRFLOW.
2. SEE 700 SERIES DRAWINGS FOR CONTROLS DETAILS.
3. VAV BOX TO INCLUDE HOT WATER REHEAT COIL. COIL TO BE SIZED FOR MAX AIR PRESSURE DROP OF 0.5" W.C.
4. VAV BOX TO HAVE INSULATED BOTTOM ACCESS DOOR UPSTREAM OF COIL WITH SNAP LATCH FASTENERS.
5. SEE DETAIL 4D/M-503.

SPLIT SYSTEM FAN COIL UNIT SCHEDULE

IDENTITY DATA				LOCATION		DIMENSIONS			COOLING DATA				ELECTRICAL DATA					
MARK	MANUFACTURER	MODEL	WEIGHT (LBS)	#	NAME	L	W	H	TOTAL COOLING (BTUH)	COOLING TONS (BTUH)	MIN AIR FLOW	MAX AIR FLOW (°F)	REGRIGERANT TYPE	VOLTS (V)	PHASE	FREQUENCY (HZ)	MCA	MOCP	NOTES
FCU-1	MITSUBISHI	PKA-A12HA7	29	AM101	IDF	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6
FCU-2	MITSUBISHI	PKA-A12HA7	29	BM100	ELEC	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6
FCU-3	MITSUBISHI	PKA-A12HA7	29	BM120A	ELEC	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6
FCU-4	MITSUBISHI	PKA-A12HA7	29	BM114	IDF	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6
FCU-5	MITSUBISHI	PKA-A12HA7	29	BM214	IDF	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6
FCU-6	MITSUBISHI	PKA-A12HA7	29.	BM300	IDF	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6
FCU-7	MITSUBISHI	PKA-A12HA7	29	BM314	IDF	36"	10"	12"	12,000	1	290	425	R410A	208	1	60	1	15	1-6

SPLIT SYSTEM FAN COIL UNIT SCHEDULE NOTES:

1. FAN COIL UNIT SHALL HAVE CONDENSATE PUMP TO PUMP CONDENSATE TO CONDENSATE DRAIN PIPING OR MAINS. SEE PIPING DRAWINGS.
2. UNIT DISCONNECTS ARE TO BE PROVIDED BY DIV. 26.
3. ALL INTERLOCKING WIRING BETWEEN INDOOR UNIT AND OUTDOOR UNIT PROVIDED BY DIV. 23 COORDINATE ALL MAIN POWER WIRING WITH DIV. 26 AS REQUIRED.
4. ALL WALL MOUNTED FAN COIL UNITS SERVING IT DATA ROOMS SHALL BE MOUNTED A MINIMUM OF 10'-0" A.F.F. AND A MINIMUM OF 1'-9" ABOVE ANY CABLE TRAYS IN ROOM.
5. PROVIDE COLOR MATCHING PIPE ENCLOSURE AS REQUIRED IF UNIT HAS SIDE REFRIGERANT OR CONDENSATE PIPING CONNECTIONS.
6. SEE DETAIL 3D/M-502.

AIR COOLED SPLIT SYSTEM CONDENSING UNIT SCHEDULE

IDENTITY DATA							COOLING DATA			ENERGY DATA		ELECTRICAL DATA						
MARK	MANUFACTURER	MODEL	WEIGHT (LBS)	LOCATION	SYSTEM SERVED	REFG. TYPE	NOMINAL COOLING (TONS)	TOTAL COOLING (BTUH)	AMBIENT DRY BULB	EER	SEER	VOLTS (V)	FREQ. (HZ)	PHASE	MCA (A)	MOCP (A)	DISCONNECT PROVIDER	NOTES
CU-1	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-1	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9
CU-2	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-2	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9
CU-3	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-3	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9
CU-4	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-4	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9
CU-5	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-5	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9
CU-6	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-6	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9
CU-7	MITSUBISHI	PUY-A12NKA7	92	ROOF	FCU-7	R-410A	1	12,000	95	12	20.8	208	60	3	11.0	28	ELECTRICAL CONTRACTOR	1-9

AIR COOLED SPLIT SYSTEM CONDENSING UNIT SCHEDULE NOTES:

1. COORDINATE LOCATION OF UNIT ON ROOF WITH ALL OTHER TRADES.
2. REFERENCE INSTALLATION DETAIL 3E/M-502.
3. UNIT SHALL BE MOUNTED ON PRE-MANUFACTURED EQUIPMENT STANDS EQUAL TO MIRO HD.
4. SYSTEM TO INCLUDE REFRIGERANT AUTO CHARGING, LEAK CHECK FUNCTION, AND AUTO ADDRESSING FUNCTION.
5. DIV. 23 TO COORDINATE REFRIGERANT PIPE ROUTING AND SIZING WITH EQUIPMENT MANUFACTURER.
6. UNIT RATED TOTAL COOLING INFORMATION IS BASED ON OUTDOOR AIR TEMPS: 95 °F / 75 °F SUMMER CONDITIONS, 47 °F / 43 °F WINTER HEATING CONDITIONS.
7. PROVIDE OPTIONAL WIND BAFFLE FOR LOW AMBIENT COOLING OPERATION DOWN TO -10 °F AMBIENT.
8. COORDINATE ELECTRIAL POWER REQUIREMENTS WITH DIV. 26.
9. COOLING ONLY SYSTEM.

ELECTRIC CABINET UNIT HEATER SCHEDULE

IDENTITY DATA				ROOM		HEATING DATA	ELECTRICAL DATA		
MARK	MANUFACTURER	MODEL	WEIGHT (LBS)	NAME	NUMBER	CAPACITY (KW)	VOLTS	PHASE	NOTES
EUH-1	QMARK	AWH44083	23	VEST	BS113A	4	208	3	

DUCT SILENCER SCHEDULE

IDENTITY DATA					DIMENSIONS			WEIGHT (LBS)	DUCT SILENCER SCHEDULE									
											MIN. INSERTION LOSSES (BY OCTAVE BAND)								
MARK	MANUFACTURER	MODEL	EQUIPMENT SERVED	AIRFLOW	H	W	L		APD (IN-WG)	FACE VELOCITY	1	2	3	4	5	6	7	8	NOTES
RA-1	PRICE	RLT60/3B	RTAHU-2	7500	24"	36"	60"	163	0.2	1,250	8	11	16	25	28	27	18	12	
RA-2	PRICE	RHT72/6E	RTAHU-1	34000	48"	72"	72"	660	0.22	1,420	10	15	21	28	32	29	18	12	
RA-3	PRICE	RMT60/6D	RTAHU-1	2400	14"	24"	60"	77	0.13	1,030	8	14	20	29	29	26	15	11	
RA-4	PRICE	RHT96/8D	RTAHU-1	10600	20"	56"	96"	363	0.1	1,360	10	13	21	28	27	21	14	11	
SA-1	PRICE	RHT60/3E	RTAHU-2	7500	20"	36"	60"	154	0.25	1,500	8	10	15	25	31	30	21	14	
SA-2	PRICE	RHT96/4A	RTAHU-1	16300	26"	40"	96"	287	0.2	2,260	8	8	13	25	28	23	14	9	
SA-3	PRICE	RHT72/6D	RTAHU-1	30700	36"	72"	72"	534	0.2	1,710	8	11	16	24	24	22	15	11	

SCHMIDT ASSOCIATES
415 Massachusetts Avenue
Indianapolis, IN 46204
www.schmidt-arch.com

Project No. 2018-050.LCH
Project Date 05.05.2020
Produced SLO / EP

SARAH KATHLEEN HEMPSTEAD REGISTERED No. AR10400134 STATE OF INDIANA ARCHITECT

Sarah K Hempstead

These Drawings and Specifications, and all copies thereof are and shall remain the property and copyright of the Architect. They shall be used only with respect to this Project and are not to be used on any other Project or Work without prior written permission from the Architect.

#	Revision	Date
1	ADDENDUM #1	05/14/2020

7300 E 56th St.
Indianapolis, IN 46226



KEY PLAN

N

MSD OF LAWRENCE TOWNSHIP

LAWRENCE CENTRAL HIGH SCHOOL RENOVATION

MECHANICAL SCHEDULES

M-605