

February 13, 2025

ZHS Locker Room Addition & PVE Site Drainage 1000 Mulberry St., Zionsville, IN 46077 & 4700 S 975 E. Zionsville, IN 46077

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications, and the Drawings dated January 21, 2025, by Fanning Howey Associates. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 1-1 through ADD 1 - 4 and attached Fanning Howey Associates, Inc. Addendum No. 01, dated February 11, 2025, consisting of 3 pages and 42 drawings.

A. 00 20 00 – INFORMATION AVAILABLE TO BIDDERS

- 1. Add the following paragraphs to be included as part of this specification section:
- B. The Subsurface Investigation & Geotechnical Recommendation prepared by Alt & Witzig Engineering, Inc. dated August 7, 2024, is included as part of Addendum 01 for reference by Bidding Contractors. This document is not a Contractual Document; however, it is included for reference and guidance to be used in relation to Work performed as part of the project.
- C. The Test Pit Investigation for Zionsville High School Locker Room Existing Foundations prepared by Alt & Witzig Engineering, Inc. dated August 8, 2024, is included as part of Addendum 01 for reference by Bidding Contractors. This document is not a Contractual Document; however, it is included for reference and guidance to be used in relation to Work performed as part of the project.
- D. Bidding Contractor question and answer log through February 12, 2025 is included as part of Addendum 01 for reference by Bidding Contractors.

E. 01 12 00 – MULTIPLE CONTRACT SUMMARY

1. Incorporate the following revisions to the Multiple Contract Summary as noted below as part of Addendum 01.

A. BID CATEGORY NO. 01 – GENERAL TRADES AT PVE

Add the specification sections: Section 04 01 20.52 – Masonry Cleaning

B. BID CATEGORY NO. 02 – GENERAL TRADES AT ZHS

Add the specification sections: Section 06 16 00 – Sheathing Section 07 95 13.13 – Interior Expansion Joint Covers Section 10 43 13 – Defibrillator Cabinets

Delete the following clarification:

13. Section 07 21 00 Thermal Insulation that is below grade shall be provided by the General Trades Contractor. Section 07 21 00 Thermal Insulation cavity wall insulation behind the masonry veneer shall be provided by the Masonry Contractor. All other Section 07 21 00 Thermal Insulation shall be provided by Drywall Contractor.

Add the following clarifications:

26. General Trades Contractor is responsible to install and maintain temporary enclosure at every exterior opening. Each opening shall receive minimum of 2x framed lumber with ³/₄" plywood. First floor exterior door openings shall be framed in lumber with adequate door hardware to allow full operation of temporary door openings for material access. All openings must be able to be locked and secured.

27. The General Trades Contractors shall include the demolition and/or removal of the temporary partitions noted in Clarification #26 upon direction of the Construction Manager. The openings will remain in place immediately following CMU masonry until permanent frames are available.

28. In regard to 06 16 00 – Sheathing, the Metal Stud, Drywall & Ceiling Contractor is responsible for the glass may gypsum sheathing. The Roofing Contractor is responsible for nailbase, sheathing and lumber required as part of their roofing system. The General Trades Contractor is responsible for all other sheathing, dan backing and wall blocking.

C. BID CATEGORY NO. 03 – MASONRY

Add the specification sections: Section 04 01 20.52 – Masonry Cleaning Delete the following clarification:

3. Section 07 21 00 Thermal Insulation that is below grade shall be provided by the General Trades Contractor. Section 07 21 00 Thermal Insulation cavity wall insulation behind the masonry veneer shall be provided by the Masonry Contractor. All other Section 07 21 00 Thermal Insulation shall be provided by Drywall Contractor.

Add the following clarification:

8. As part of specification section 07 21 00 – Thermal Insulation, the Masonry Contractor is responsible for mineral wool insulation, spray foam insulation and sealant at top of masonry wall conditions to close any gaps or voids at structure or adjacent surface intersections.
9. Masonry Contractor shall clean all existing masonry surfaces that become exposed interior surfaces.

E. BID CATEGORY NO. 05 - ROOFING

Add the specification sections: Section 06 16 00 – Sheathing

Add the following clarification:

5. In regard to 06 16 00 – Sheathing, the Metal Stud, Drywall & Ceiling Contractor is responsible for the glass may gypsum sheathing. The Roofing Contractor is responsible for nailbase, sheathing and lumber required as part of their roofing system. The General Trades Contractor is responsible for all other sheathing, dan backing and wall blocking.

F. BID CATEGORY NO. 06 - METAL STUDS, DRYWALL & CEILINGS

Delete the following clarification:

2. Section 07 21 00 Thermal Insulation that is below grade shall be provided by the General Trades Contractor. Section 07 21 00 Thermal Insulation cavity wall insulation behind the masonry veneer shall be provided by the Masonry Contractor. All other Section 07 21 00 Thermal Insulation shall be provided by Drywall Contractor.

Add the following clarification:

8. As part of specification section $07\ 21\ 00$ – Thermal Insulation, this Contractor is responsible for mineral wool insulation, spray foam insulation and sealant at top of metal stud wall conditions to close any gaps or voids at structure or adjacent surface intersections.

9. In regard to 06 16 00 – Sheathing, the Metal Stud, Drywall & Ceiling Contractor is responsible for the glass may gypsum sheathing. The Roofing Contractor is responsible for nailbase, sheathing and lumber required as part of their roofing system. The General Trades Contractor is responsible for all other sheathing, dan backing and wall blocking.

K. BID CATEGORY NO. 11 – FIRE SUPPRESSION

Add the following clarification:

10. Contractor is responsible for joint sealing all of their penetrations. This is to include any necessary acoustic joint sealants.

L. BID CATEGORY NO. 12 – PLUMBING & HVAC

Add the following clarification:

8. Contractor is responsible for joint sealing all of their penetrations. This is to include any necessary acoustic joint sealants.

M. BID CATEGORY NO. 13 – ELECTRICAL & TECHNOLOGY

Add the following clarification:

9. Contractor is responsible for joint sealing all of their penetrations. This is to include any necessary acoustic joint sealants.

ctivity Name	Original Start	Finish		2025											2	026							
	Duration		Feb	Mar	Арі	· May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	C
ZHS Locker Room Addition & PVE Site Drainac	685 26-Feb-25 A	23-Oct-26	6								Г 												-
Project Administration	685 26-Feb-25 A	23-Oct-26	1	-					 					1						-			di se
Milestone Dates	685 26-Feb-25 A	23-Oct-26		-	1	1		1	l I	1	1	1	1	1	1	1	1	1	1		1	1	;
Bid Date	0 26-Feb-25 A		•	🔶 Bid D	ate				1				1	1				-					-
Notice to Proceed	0 12-Mar-25*			• N	lotice to	Proceed					1	1											
ZHS Locker Room Addition Mobilization	0 02-Jun-25*		11				🔶 ZHS	Locker R	Room Ad	dition M	bilizatio	n		+				 	-				
PVE Mobilization	0 02-Jun-25*						PVE	Mobilizat	tion			1	1					-					
PVE Site Drainage - Substantial Completion	0	11-Aug-25*							PV	E Site D	rainage	- Substa	ntial Co	mpletion	n								
ZHS Temporary Enclosure & Weathertight	0	14-Oct-25							- - - -		♦ Z⊦	IS Tem	orary Er	closure	& Weat	thertight		-					
Temporary Heat Available	85 17-Nov-25*	18-Mar-26							 			Δ	1	1	1		Tempora	y Heat	Available	e			-
ZHS Permanent Enclosure	0	23-Jan-26												•	ZHS P	ermane	nt Enclos	sure					
ZHS Permanent Power	0	20-Mar-26														•	ŻHS Pe	manent	Power				i
ZHS Locker Room Renovation	0 06-Apr-26*								1 1 1	1	1	1 1 1	 	1			🔶 ZHS	Locker	Room F	Renovat	lion		
ZHS Permanent HVAC	0	22-May-26							1 1 1		1	1	1					•	ZHS Pe	ermaner	nt HVAC		-
ZHS Locker Room Addition - Substantial Completion	0	19-Jun-26*						¦ 	 	¦ 	 			¦ 				¦ 	<u> </u>	ZHS Lo	cker Roc	om Addit	ion - :
ZHS Locker Room Addition - Owner Furniture & Occupancy	15 13-Jul-26	31-Jul-26									1				į			-		Δ	ZHS	Locker	Room
ZHS Locker Room Renovation - Substantial Completion	0	11-Sep-26*							1 1 1		 	1 1 1	 						- - -			♦ Z	HS L
Final Completion	0	02-Oct-26							1									-					◆ F
ZHS Locker Room Renovation - Owner Furniture & Occupancy	15 05-Oct-26	23-Oct-26										1											
Material Procurement / Submittals	120 12-Mar-25	28-Aug-25					+			28-Au	g-25, Ma	terial Pr	cureme	ht / Sub	mittals			; ;					
Long Lead Material Submission	10 12-Mar-25	25-Mar-25			Long	Lead Ma	terial Su	bmission	1 1 1			1											-
General Submittals	40 12-Mar-25	06-May-25				V Ge	neral Su	bmittals	1		1	1											
	10 26-Mar-25	08-Apr-25		4		ritical Sub	brittal Re	eview			1	1											i
General Submittal Review	40 26-Mar-25	20-May-25		4			Ģeneral	Submitta	al Reviev	NY Ny lanaul		Annial Du	 						- - -				
Concern Material Procurement	50 22 Apr 25	20-Aug-25	+		···	<u></u>			v vrol Moto					61L +									
DVE Site Drainage Improvemente	65 02-lup-25	02-Jui-23					1	y Gene				VE Site) Drainade		¦ Imento			-					-
PVE Site Drainage improvements	00 02-001-20	02-06p-20							0 - 1 +	<u> </u>	sp-20, 1			, inprov	- -								
Perform Selective Architectural / Building Demolition	20 02-Jun-25	27-Jun-25						Perform	n Select	ive Archi	tectural /	Building	Demoli	țion ¦									
Perform Selective Site Demolition	30 02-Jun-25	14-Jul-25					:	Pe	erform Se	elective	Site Dem	nolition						-	1 1 1				-
Install Gutters & Downspout	25 16-Jun-25	21-Jul-25							Install G	utters & I	Downspo	out	 										-
Perform Masonry Cleaning	30 16-Jun-25	28-Jul-25						V	Perforr	n Masor	iry Clear	ling	 	+	, , ,							·	
Prep & Pour Concrete Sidewalks	40 16-Jun-25	11-Aug-25							Pre	ə̈́p & Ροι	r Concre	ete Side	walks						1 1 1				
Install Downspout Connections & Drains	30 23-Jun-25	04-Aug-25					Δ		🔽 Insta	d Downs	pout Co	nnectio	is & Dra	ins				1					
Punchlist & Corrections	15 12-Aug-25	02-Sep-25								V Punc	hlist & C	orrectio	ns					-					
ZHS Locker Room Addition & Renovation	345 02-Jun-25	02-Oct-26	1															-					– 0
Sitework	285 02-Jun-25	10-Jul-26	 				-+	-,						÷					- +	10)-Jul-26, 3	Sitework	-¦
Mobilize & Establish Jobsite Perimeter	5 02-Jun-25	06-Jun-25					📉 Mo	bilize & E	stablish	Jobsite I	erimete	r						-					
Selective Demolition & Site Demolition (East/West Drive)	10 09-Jun-25	20-Jun-25						Selective	Demoli	tion & Si	te Demo	lition (E	ast/West	Drive)									
Establish Building Pad	5 23-Jun-25	27-Jun-25	1					🖌 Establi	sh Buildi	ing Pad	1		 										
Install Water Utilities	15 23-Jun-25	14-Jul-25					Δ	📩 🗸 Ins	stall Wat	k ¢rUtilitie	5	 											
Existing Structure Demolition	30 23-Jun-25*	04-Aug-25	11				Δ		V Exist	ting Strue	ture Dei	molition		+									
Install Storm Utilities	15 12-Aug-25	02-Sep-25								🔽 Insta	Storm l	Jtilities											
Install Sanitary Sewer Utilities	15 03-Sep-25	23-Sep-25							1 1 1		Install S	anitary	Sewer Ut	liities						1 1 1			
Establish Subgrade (East/West Drive)	5 24-Sep-25	30-Sep-25		1 1 1				1 	1 1 1		Estab	lish Sub	ģrade (E	ast/Wes	t Drive)			- - -		1			
Place Concrete Curbs (East/West Drive)	5 01-Oct-25	07-Oct-25	 					, , -,		¦	🚺 Plac	e Conc	rete Curt	⊳s (East/	/West D)rive)		¦		¦			
Place Asphalt Stone & Binder (East/West Drive)	2 08-Oct-25	09-Oct-25		i 1	1				1	1	🛛 Pla	ce Asph	alt Stone	& Binde	er (East	/West D	rive)	1		1	1		
Actual Work				Z	HS L	.ocker	Roo	m Ado	dition	PVE	Site I	Drain	ade										
✓ Remaining Work													55									SKI	LLM
Critical Remaining Work							^	. !	0-1-	l	1												
Milestone							Guid	eine	s Sch	ieau	ie											31	
Summary								Page	e 1 of 4														

					20	126						-	202	07	
	Feb	Mar	Apr	Mav	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr
	100	IVICI	Дрі	way	Juli	001	Aug	Ocp	000	23-Oct-2	26. ZHS	Locker R	l CD	dition &	PVE
											,				
										23-Oct-2	26, Proje	ct Admin	istration		
	· · · ·				1	1	1			23-Oct-2	26, Miles	tone Dat	es		
					1					1					
					T	 									
					1										
n					1										
e é	& Weath	ertight													
	i i	Т	emporar	v Heat A	vailable										
-	ZHS Pe	rmanen	t Enclos	, re	+										
		• 7	HS Pen	manent	Power										
		• -	♦ 7HS	Locker	Room R	enovatio	n								
			• 2110		7HS Pe	manent	HV/AC								
				•		HSION	ker Roor	h Additio	n - Sube	tantial (: Completiv	hn			
-					· ▼ 2 ¦		7 7491	ocker D		dition 0		niture 8		ncv	
							, 200 L		S Locks	Room			etantia	Comple	tion
								▼ 2⊓		Complet	i venoval	JUL - OUL	งจเสเทเส	Comple	suori
										- reuc		m Don-	votion	Oumer F	
										ZHS LO	cker Roo	m Reno	vation -	Owner F	umitu
on	nittais														
					1					1					
-					! ! !										
											1				
vé	ements														
					1										
1					1						1				
					•										
					1										
										1	1				
									02-00	t-26, Z⊦	S Locke	r Room /	Addition	& Reno	vation
-						10-	Jul-26 S	itework							
-					1		Jui 20, C			1					
					 					 		- - -			
-					; ; ;										
					1						1				
st	Drive)				1 1 1										
t/\	/Vest Dr	ive)													
le	r (East/\	Nest Dri	ve)		 					 	I I I				
							1								
								CKII							
								SKIL	LMAN						
							R	1	Π						
						C			11						

ne	Original Start	Finish					202	25									_		2026)						202	27
	Duration		Feb	Mar /	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep Oct	Nov	Dec	Jan	Feb	Mar
Perform Full Depth Asphalt Demolition	5 01-Jun-26*	05-Jun-26		1				1						1	-			4	Perform	າ Full De	epth Aspl	halt Demolit	ion			1	
Mill Existing Parking Lot	2 08-Jun-26	09-Jun-26																	🛛 Mill Ex	isting	arking Lo	ot					
Establish Parking Lot Subgrade	5 08-Jun-26	12-Jun-26						1											🛿 Estab	olish Par	king Lot	Subgrade					
Place Concrete Curbs & Walks	20 15-Jun-26	10-Jul-26																		7 Plaçe	Concret	te Curbs & V	Valks				
Install Landscaping & Site Furniishings	15 22-Jun-26	10-Jul-26				1		1						1			1	1		7 Install	Landsc	aping & Site	Fumiishir	nģs	1		
Place Asphalt Stone & Binder	5 29-Jun-26	03-Jul-26	1	1			1	1												Place A	sphalt St	tone & Bind	ər				
Place Surface Coat Asphalt	2 06-Jul-26	07-Jul-26	1					i						1					Σ	Place	Surface	Coat Áspha	lt				
Install Pavement Markings	2 08-Jul-26	09-Jul-26	1	1				1											Δ	7 Install	Paveme	ent Markings	;			1	
Building Addition	265 30-Jun-25	10-Jul-26		i I I			4) 10-Ju	I-26, B <mark>ui</mark> l	lding Ádditio	n				
Building Core & Shell	145 30-Jun-25	23-Jan-26					4								23-Jar	1-26, Bui	ding Cor	e & Shel					·				
Place Wall Footings & Spread Foundations	15 30-Jun-25	21-Jul-25					4		Place Wa	all Footin	gs & Sp	read Fou	ndation	s													
Install Underground Electrical Rough-In	10 22-Jul-25	04-Aug-25	1	1					🗸 Insta	ll Underg	pround E	lectrical	Rough-l	n													
Install Underground Plumbing Rough-In	15 22-Jul-25	11-Aug-25	1	1			1	Δ	🔽 Inst	tall Unde	erground	Plumbir	ng Roug	h-In													
Erect Structural Steel Members	15 22-Jul-25	11-Aug-25	1	1					E re	ct Struct	ural Stee	el Memb	ers	1													
Erect Structural Joists & Deck	10 12-Aug-25	25-Aug-25								Erect St	ructural	Joists &	Deck	+			-		·				· i		+		+ ! !
Detail Structural Steel	10 26-Aug-25	09-Sep-25	1					1		🗾 Det	ail Struct	tural Stee	el														
Install Exterior Door Frames	15 26-Aua-25	16-Sep-25	1						Δ	□ V In	stall Exte	erior Doc	or Frame	Ś			-				į						
Install Masonry Shaft & Exterior Wals	25 26-Aua-25	30-Sep-25	1					1			/ Install	Masonn	/ Shaft &	k Exterio	wals												
Prep & Place Slab on Deck	10 03-Sep-25	16-Sep-25	-					1	_		rep & Pla	ace Slab	on Dec	k	-												
Install Roofing Insulation & Membrane	20 10-Sep-25	07-Oct-25	++								V Insta	all Roofin	na Insula	tion & N	/ /embra	ne			·				·				
Prep & Place Slab on Grade	15 17-Sep-25	07-Oct-25	-			1		1			Prer	% Place	s Slab or	n Grade				1	1							1	
Set Temporary Enclosures at Doors & Windows	10 01-Oct-25	14-Oct-25	-	1			1					t Tempo	ranvEnc		¦ at Doo	rs & Win	awor										
Set Roofton Equipment	5 08-Oct-25	14-Oct-25	-	1			1	1				t Rooftd	n Fauin	ment	1					1			1	-			
Install Interior Door Emmos	15 08 Oct 25	28 Oct 25	-	1				1					p Equip ntorior F	hoor Era	mos												
	15 08 Oct 25	20-001-25	++ +						 				Poofing	Flaching	1/103		-		·	·			·		+		
Install Interior Masonny Wolk	20 08 Oct 25	20-00-25	-	1				1				V Install	1. Untorio	Masan													
	20 05 Nov 25	04-1100-25	-	1				1			△					oor											1
	10 20 Doo 25	04-Dec-23	-	1								Δ	y msta				orofront	8 Windo	4 Eromdo								
Set Exterior Deem & Claring	10 29-Dec-23	09-Jan-20	-	1			1	1								dorior De										1	
Set Exterior Doors & Glazing	10 12-Jaii-20	23-Jan-20				·									Seles		ψis α Gi	azing				rior Duildou					
	210 17-Sep-25	10-Jul-20	4	1			1	1					lu at all D		Dava		1			<u> </u>	1-20, Inte						
Install Plumbing Rough-In	50 17-Sep-25	25-NOV-25	-	 				i						niamul ⁻	, Roug	nəin											
	50 17-Sep-25	25-INOV-25	-	1				1				V	Install E		Rougr	i-in											
Install Temporary Roof Drain Systems (or permanent)	5 08-Oct-25	14-Oct-25	-					1				stali iem	porary R	koot Dia	in Syste	ems (or p	ermanei	ιτ)									
	50 08-Oct-25	18-Dec-25												istali Du	ICTWORK	& HVAC	Equipme	ent 	·				·			 	
Install Low Voltage & FA Rough-In	40 15-Oct-25	11-Dec-25	-	1				1				! ! 	Ins	tall Low	Voltage		ougn-in			1							
Install Electrical & Data Wall Boxes	30 29-Oct-25	11-Dec-25		1			1	1			Δ		Ins	tall Elec	trical &	Data Wa	Boxes										
Install Fire Protection System	30 05-Nov-25	18-Dec-25		1								<u> </u>	V Ir	hstall Fir	e Prote	ction Sys	tem			1							
Apply Block Fill & Primer	20 26-Nov-25	26-Dec-25		1			1	1			_		V	Apply I	Block Fi	II & Prime	er						1			1	
Pull Power Cabling	20 12-Dec-25	09-Jan-26	_						 		🛛 Plac	ce Aspha	It Stone	Bind	er (East	/West D	ive)		·								
Install Duct & Pipe Insulation	20 19-Dec-25	16-Jan-26		1			1	1							hstall D	uct & Pip	ė Insulat	ion								1	
Install HVAC Controls	25 19-Dec-25	23-Jan-26						1					Δ		Install	HVAC C	ontrols										
Pull Low-Voltage & Data Cabling	20 12-Jan-26	06-Feb-26		1				1						Δ	🔽 Pu	III Low-Vo	ltage & I	ata Cab	oling							1	
Apply First Coat Paint	25 19-Jan-26	20-Feb-26						1								Apply F	irst Coat	Paint	1								
Install 1st Floor Ceiling Grid	20 02-Feb-26	27-Feb-26												, , , ,		💙 Instal	1st Floo	r Ceiling	Grid								
Install Fire Alarm Devices	20 09-Feb-26	06-Mar-26		1		1	1	1								V Inst	all Fire A	arm Dev	ices		1						
Install Registers, Grilles & Diffusers	15 16-Feb-26	06-Mar-26					1	1						1		V Inst	all Regis	ters, Grill	es & Diffus	ers							
Install 1st Floor Lighting	20 16-Feb-26	13-Mar-26				1	1									🔽 In	stall 1st l	loor Ligh	nting								
Startup HVAC System	10 23-Feb-26	06-Mar-26	1	1 1 1				1				· · · · · · · · · · · · · · · · · · ·		1	1 4	🔽 Sta	tup HVA	C Syster	n					1			

Actual Work	ZHS Locker Room Addition PVE Site Drainage	
Remaining Work		
Critical Remaining Work		
♦ ♦ Milestone	Guideline Schedule	
Summary	Page 2 of 4	



e	Original Start	Finish					20)25													2026								2	2027	7
	Duration		Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jar	n Fe	eb N	Mar	Apr	Ma	y Jur	ı J	ul A	Nug	Sep	Oct	Nov	Dec	Jan	Feb	b	N
Paint 2nd Floor Exposed Structure	15 23-Feb-26	13-Mar-26									1						🗸 Pa	int 2nd	Floor	Exposed	Struct	ure								_	
Install Decorative Resinous Flooring	20 23-Feb-26	20-Mar-26				 			-!		L	-!						nstall D)ecora	tive Resi	noùs Fl	ooring			L ! !	-!					
Make Up Electrical Wall Devices	20 23-Feb-26	20-Mar-26	-			1			1							Δ		/lake U	Jp Elec	trical Wa	I Devic	es				-			-		
Install 2nd Floor Lighting	10 16-Mar-26	27-Mar-26	-			1			1		1	1						Install	l 2nd F	loor Ligh	ting				1 1 1						
Install Casework	10 16-Mar-26	27-Mar-26	-			1			1		1					-		Install	l Ċase	work	-				1				-		
Install Lockers	25 16-Mar-26	17-Apr-26	-			1			1 1 1		1	1							Install	Lockers	-				1 1 1				-		
Install Epoxy Flooring	10 23-Mar-26	03-Apr-26		- L L - I I I I							L					 !	\sim	✓ Instant	all Epc	xy Floori	ng	!			L I					L I I	
Set Plumbing Fixtures	20 23-Mar-26	17-Apr-26	-			1			1										Set Plu	umbing F	ixtures				, , ,				-		
Install Polyurethane Gymnasium Floor	15 30-Mar-26	17-Apr-26	-								1								Install	Polyureth	nane G	ymnasiu	um Flo	oor							
Place Restroom Partitions & Accessories	20 06-Apr-26	01-May-26	-						 		- - - -								; V Pla	ace Rest	oom P	artitions	; & Acc	cessorie	s						
Install Rubber Floor Tiling	10 20-Apr-26	01-May-26	-			1			1		1							$\overline{\Lambda}$	_ V Ins	stal	ber Floo	or Tilina									
Install Ceiling Pads	20 20-Apr-26	15-May-26																		Install (Ceilina	Pads								·	
Perform HVAC Commissioning & TAB	25 20-Apr-26	22-May-26	-			1					1	1							1	V Perfo	m:HV/	AC Com	missic	onina &	TAB				-		
Apply Final Paint	15 04-May-26	22-May-26	-			1										i					Final F	Paint		orning a		-				i	
Hang Wall Mounted Boards & Equipment	15 04-May-26	22-May-26	-			1					1									V Hand	Wall N	launited	Boah	ds & Fo	¦ luinmen	ť					
	15 18_May_20	05- lun-26				1			1 1		1 1		 								stall Sc	black	Floorin	na na	(aprilo)						
	10 25 May 26	05-001-20							 _		 	 -					!				etall D				 					L 	
Hang Deer Slahe & Set Hardware	10 20-Way-20	10 Jun 26	-			1			1												รเล่แ Da	a Door S		les 8 Sot L	lordword						
Dunchlist & Corrections	10 00-Juli-20	19-Juli-20	-								1															5					
Punchilist & Conections	13 22-Juli-26	10-Jul-26							- - - -		1											Punchi	ist a c	Jonecu		4 26 1	obkor D		, ndvatio		
Ocker Room Renovations	130 06-Api-26	02-00-26				1					1								1	1	1	-				GI-20, L		om Re	novalio	ns	
	130 06-Apr-26	02-Oct-26	44													<u>-</u>	·								02-0	'¢t-26, II -¦	ntenor R	enovatio	on; 		
	15 U6-Apr-26	24-Apr-26	_			1			1		1								Perio	orm Sele			n ¦		1						
	15 13-Apr-26	01-May-26	_																	ITOM IVIL	P Den	nolition	i							į	
Install Masonry Walls	15 27-Apr-26	15-May-26	_			1					1							4		Install N	lason	/ Walls									
Install Ductwork & HVAC Equipment	15 04-May-26	22-May-26	_													į				Instal	Ductw	ork & H	VACE	Equipm	ent	Ì				į	
Install Plumbing Rough-In	20 04-May-26	29-May-26									 						!			V Inst	all Plun	nbing R	ough-	ln 	 						
Install Electrical Rough-In	20 04-May-26	29-May-26														į			Δ	Ninst	all Elec	trical Ro	ough-li	n	1					į	
Apply Block Fill & Primer	15 18-May-26	05-Jun-26	_			1			1		1								4		oply Bl	ock Fill 8	& Prime	er	1				-		
Install Duct & Pipe Insulation	15 25-May-26	12-Jun-26	_																		Install	Duct & F	Pipe (r	nsulatio	n					i	
Install HVAC Controls	15 25-May-26	12-Jun-26				1			1		1										Install		Control	ls	1	-			-		
Install Fire Protection System	20 01-Jun-26	26-Jun-26																			V Ins	tall Fire	Protec	ction Sy	/stem					!	
Install Low Voltage & FA Rough-In	20 01-Jun-26	26-Jun-26	_			1					1									<u> </u>	V Ins	tall Ļow	Volta	ge & FA	Rough	i-In					
Apply First Coat Paint	15 15-Jun-26	03-Jul-26																			– 7	pply Firs	st Coa	at Paint						Ì	
Install Electrical & Data Wall Boxes	20 15-Jun-26	10-Jul-26				1														Δ		Install E	Electric	cal & D	ata Wa l	Boxes					
Install Ceiling Grid	15 29-Jun-26	17-Jul-26																			Á	🗸 Instal	ll Ceili	ng Grid	1					į	
Install Decorative Resinous Flooring	15 06-Jul-26	24-Jul-26		-							, , ,											🔽 Ins	tall De	ecorativ	e Resin	ous Flo	oring			 	
Make Up Electrical Wall Devices	15 06-Jul-26	24-Jul-26				1			1		1					1					Δ	🔽 Ma	ike Up	Electri	cal Wall	Device	s				
Install Registers, Grilles & Diffusers	10 13-Jul-26	24-Jul-26				1			1 1 1		1 1 1				-	1					Δ	Inst	tall Re	egisters	Grilles	& Diffu	sers				
Pull Power Cabling	15 13-Jul-26	31-Jul-26				1			1 1 1		1			1						1	Δ	Ý P	ull Po	wer Ca	bling				1		
Install Lighting	15 13-Jul-26	31-Jul-26				1			1 1 1		1 1 1										Δ	🕂 İr	nstall	Lighting	(
Install Epoxy Flooring	10 27-Jul-26	07-Aug-26	1			1			1 1 1		1			-									Instal	∥ Ероху	Floorin	ģ					
Set Plumbing Fixtures	15 27-Jul-26	14-Aug-26	11	- L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L L					-!		L	-l	J								· 		🗸 Set	Plumb	ing Fixtu	ures	- 4			L 	•
Pull Low-Voltage & Data Cabling	10 03-Aug-26	14-Aug-26				1			1		1												🗸 Pull	I Low-V	oltage 8	bata (Cabling				
Install Casework	10 03-Aug-26	14-Aug-26				1			1 1 1		1 1 1												🗸 Inst	tall Cas	ework						
Install Lockers	15 03-Aug-26	21-Aug-26				1			1		1					1					1		🔽 İn	nstall Lo	ckers	-			-		
Place Restroom Partitions & Accessories	15 03-Aug-26	21-Aug-26				1			1 1 1		1 1 1			1		1					1 1 1		T P	lace Re	stroom	Partitio	ons & Acc	essories	5		
Install Ceiling Pads	10 10-Aug-26	21-Aug-26									L				 !	 	·				·	Δ	🔽 İn	nstall Ce	eiling Pa	ads					
Apply Final Paint	10 10-Aug-26	21-Aug-26			1	1			1			1	1	1			-		1					nnh (Fir		; +'			-		

	Act
	-

▲ V Remaining Work Critical Remaining Work

• Milestone

Summary

ZHS Locker Room Addition PVE Site Drainage

SKILLMAN

Guideline Schedule

Page 3 of 4

Activity Name Original Start				Finish	2025 2026											2027															
		Duration			Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr
	Install Fire Alarm Devices	15	17-Aug-26	04-Sep-26							1				.			Î					Δ	V Insta	all Fire Al	arm Devi	ices				
	Install Rubber Floor Tiling	10	24-Aug-26	04-Sep-26														1			1	1	Δ	丼 Insta	all Rubbe	r Floor T	iling				
	Install Softgood Flooring	10	24-Aug-26	04-Sep-26											 						 	1	Δ	📩 Insta	all Softgo	bd Floor	ing				
	Install Data Wall Devices	10	24-Aug-26	04-Sep-26	1	· · · · · · · · · · · · · · · · · · ·			;								· · · · ·	1			 - - -		Δ	💙 Insta	all Data \	Vall Devi	ces				
	Hang Door Slabs & Set Hardware	10	24-Aug-26	04-Sep-26				1 1 1	1 1 1						1 1 1			1		1	 	 	Δ	丼 Han	ģ Door S	abs & S	et Hard	ware			
	Hang Wall Mounted Boards & Equipment	15	24-Aug-26	11-Sep-26				1							1 1 1			1			1	1		Ha	ang Wall	Mounted	Boards	& Equip	ment		-
	Punchlist & Corrections	15	14-Sep-26	02-Oct-26											- - 			1	1	1	1	1 1 1	- - - -		Punc	hlist & Co	orrection	S			

	Actual Work
Δ V	Remaining Work
	Critical Remaining Work
• •	Milestone
	Summary

ZHS Locker Room Addition PVE Site Drainage

Guideline Schedule

Page 4 of 4



ADDENDUM NO.1

Zionsville Community High School Athletic Locker Room Additions

Pleasant View Elementary School – Site Drainage Improvements

Zionsville Community Schools Zionsville, Indiana

> Project No. 224018.00 Project No. 223126.00

Index of Contents

Addendum No. 1, 11 items, 3 pages

New Project Manual Sections: 07 95 13.13 – Interior Expansion Joint Cover Assemblies and 10 43 13 – **Defibrillator Cabinets** New Drawing Sheet: S4-05

Revised Drawing Sheets: Index, G1-01, G2.00, A-00, AP-01, AD-01, AD-02, A-11, A-12, AC-11, AC-12, AR-01, A2-01, A3-01, A3-02, A3-03, A3-04, A3-05, A3-10, A3-11, A3-12, A4-02, A4-03, A5-02, A6-01, A6S-01, AI-11, AI-12, AI-22, AQ-11, AQ-12, AQ-61, E-02, E-61, ED-11, ED-12, EF-11, EL-11, EL-12, EP-11, EP-12 and ET-11 Geotechnical Report **Existing Foundation Investigation Report** Pre-Bid Clarification Log

Date: February 11, 2025

I hereby certify that this Addendum was prepared by me or under my direct supervision and that I am a duly registered Architect/Engineer under the Laws of the State of Indiana.

FANNING/HOWEY ASSOCIATES, INC. ARCHITECTS/ENGINEERS/CONSULTANTS



Paul A. Miller Registration Number AR10800161

TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 1 to Drawings and Project Manual, dated January 24, 2025, for Zionsville Community High School Athletic Locker Room Additions and Various Projects for Zionsville Community Schools, 900 Mulberry Street, Zionsville, Indiana, 46077; as prepared by Fanning/Howey Associates, Inc., Indianapolis, Indiana. This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

Each bidder shall acknowledge receipt of this Addendum in his proposal or bid.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum. (This includes miscellaneous items at the very end of this Addendum.)

RE: ALL BIDDERS

ITEM NO. 1. PROJECT MANUAL, TABLE OF CONTENTS

- A. Page 00 00 20-3, DIVISION 07: Add Section 07 95 13.13 Interior Expansion Joint Cover Assemblies
- B. Page 00 00 20-4, DIVISION 10: Add Section 10 43 13 Defibrillator Cabinets.

ITEM NO. 2. <u>NEW PROJECT MANUAL SECTIONS</u>

A. New Project Manual Sections 07 95 13.13 – Interior Expansion Joint Cover Assemblies and 10 43 13 – Defibrillator Cabinets are included with and hereby made a part of this Addendum.

ITEM NO. 3. PROJECT MANUAL, SECTION 00 20 00 - INFORMATION AVAILABLE TO BIDDERS

- A. Add paragraph B., as follows:
 - "B. The Soils Exploration Report and Soil Boring Logs were prepared for the Owner by Alt & Witzig Engineering, Inc., 4105 West 99th Street, Carmel, Indiana 46032 for use in design. The following Subsurface Investigation Report is not a part of the construction Contract Documents and is enclosed within this document for informational use only.
 - 1. The opinions expressed in this report are those of a geotechnical engineer and represent interpretations of subsoil conditions, tests, and results of analyses conducted by geotechnical engineer.
 - The enclosed report and Log of Borings, and any interpolations of conditions between test borings is not a warrant or guarantee by the Owner or Architect/Engineer of subsurface conditions.
 - 3. The Contractor should visit the site and acquaint himself with all existing conditions. Prior to bidding, bidders may make their own subsurface investigations to satisfy themselves as to the site and subsurface conditions, but such subsurface investigations shall be performed only under the time schedules and arrangements approved in advance by the Owner. Any additional information, needed by the Contractor, shall be obtained by the Contractor at no cost to the Owner.
 - 4. Structural design has been based on the report and assumes that existing soils are clean and can be compacted and will achieve the densities specified in the earthwork section. It shall be the Contractor's responsibility to determine for himself existing Site and or soil conditions.
 - 5. Additional investigation information concerning the existing foundations is also included for reference.

ITEM NO. 4. PROJECT MANUAL, SECTION 05 50 00 - METAL FABRICATIONS

- A. Replace 2.11, B., 1., as follows:
 - "1. Type 3A: Model #503A tubular rail low parapet access ladder with platform."
- B. Delete 2.11, B., 2., in its entirety.

ITEM NO. 5. PROJECT MANUAL, SECTION 09 21 16 - GYPSUM BOARD ASSEMBLIES

- A. Delete 2.1, A., 1., in its entirety.
- B. Delete 2.6, B., in its entirety.
- C. Replace 3.10, B., 6., b., as follows:
 - "b. Provide this level over impact resistant gypsum board on large bulkheads in the 2nd floor activity area. Multiple layers of Level 5 finish process may be required due to absorption of gypsum board panels."

ITEM NO. 6. PROJECT MANUAL, SECTION 09 67 23 – DECORATIVE RESINOUS FLOORING

- A. Article 1.1, C: Delete "<u>quartz and</u>" between "colored" and "flakes/chips" in first sentence.
- B. Delete 2.3, B., 1., a., in its entirety.
- C. Replace 2.3, C., 1., e., as follows:
 - "e. Aggregates: Vinyl Flake."

ITEM NO. 7. PROJECT MANUAL, SECTION 09 96 00 - HIGH-PERFORMANCE COATINGS

- A. Add 3.9, A., 3., as follows:
 - "3. Epoxy/Epoxy/Polyurethane system: (Code #5.331).
 - a. Prime Coat: Primed as part of work for Division 05 Section "Structural Steel Framing".
 - b. Intermediate Coat:
 - 1) Tnemec Series N69, Hi-Build Epoxoline at 2.0 to 3.0 mils d.f.t.
 - 2) PPG; Amerlock 600 at 3.0 to 4.0 mils d.f.t.
 - 3) Sherwin Williams; Macropoxy 646
 - c. Topcoat:
 - 1) Tnemec Series 1094 Endura-Shield at 3.0 to 4.0 mils d.f.t., gloss.
 - 2) PPG Durethane DTM Polyurethane Gloss at 3.0 to 4.0 mils d.f.t.
 - 3) Sherwin Williams; Hi-Solids Polyurethane B65W at 3.0 to 4.0 mils d.f.t.
 - d. Applications include, but is not limited to:
 - 1) Exposed structural (existing) steel columns or beams."

ITEM NO. 8. PROJECT MANUAL, SECTION 10 14 19 – DIMENSIONAL LETTER SIGNAGE

- A. Replace 2.2, A., 5., a., as follows:
 - "a. Powder-Coat Finish: Custom color to match "school color" as supplied by A/E and Owner."

ITEM NO. 9. PROJECT MANUAL, SECTION 32 17 13 – PARKING BUMPERS

- A. Add 1.1 B., as follows:
 - "B. Decorative concrete bollard."
- B. Add 2.1, B., as follows:
 - "B. Decorative concrete bollard: As indicated and detailed on the Drawings."

ZIONSVILLE COMMUNITY HIGH SCHOOL ATHLETIC LOCKER ROOM ADDITIONS

ITEM NO. 10. NEW DRAWING SHEET

A. Drawing Sheet No. S4-05 – Masonry Wall Elevations is included with and hereby made a part of this Addendum.

ITEM NO. 11. REVISED DRAWING SHEETS

A. Drawing Sheets: Index, G1-01, G2.00, A-00, AP-01, AD-01, AD-02, A-11, A-12, AC-11, AC-12, AR-01, A2-01, A3-01, A3-02, A3-03, A3-04, A3-05, A3-10, A3-11, A3-12, A4-02, A4-03, A5-02, A6-01, A6S-01, A1-11, AI-12, AI-22, AQ-11, AQ-12, AQ-61, E-02, E-61, ED-11, ED-12, EF-11, EL-11, EL-12, EP-11, EP-12 and ET-11 have been revised, dated 2/11/25, and are included with and hereby made a part of this Addendum. These Drawings supersede the original documents.

END OF ADDENDUM

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes interior expansion joint cover assemblies.
- B. Related Sections include the following:
 - 1. Division 04 Section "Unit Masonry" for masonry wall joint systems.
 - 2. Division 07 Section "Fire-Resistive Joint Systems" for liquid-applied joint sealants in fireresistive building joints.
 - 3. Division 07 Section "Preformed Joint Seals" for performed foam joint seals typically at expansion joints.
 - 4. Division 07 Section "Joint Sealants" for liquid-applied joint sealants and performed foam joint seals.

1.2 DEFINITIONS

- A. Architectural Joint System: Any filler or cover used to span, fill, cover, or seal a joint, except expanding foam seals and poured or foamed in-place sealants.
- B. Fire Barriers: Any material or material combination, when fire tested after cycling, designated to resist passage of flame and hot gases through a movement joint.
- C. Cyclic Movement: Periodic change between widest and narrowest joint widths in an automatically mechanically controlled system.
- D. Maximum Joint Width: Widest linear gap a joint system tolerates and in which it performs its designed function without damaging its functional capabilities.
- E. Minimum Joint Width: Narrowest linear gap a joint system tolerates and in which it performs its designed function without damaging its functional capabilities.
- F. Movement Capability: Value obtained from the difference between widest and narrowest widths of a joint opening typically expressed in numerical values (mm or inches) or a percentage (plus or minus) of nominal value of joint width.
- G. Nominal Joint Width: The width of the linear opening specified in practice and in which the joint system is installed.

1.3 ACTION SUBMITTALS

- A. Product Data: For each manufactured product specified, product specified, including data sheets, installation instructions, and as required templates to explain construction and to provide for incorporation of the product into the Project.
- 1.4 QUALITY ASSURANCE
 - A. Accessibility Requirements: Comply with applicable provisions in ICC A117.1.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Conspec Systems, Inc.
 - 2. Balco, Inc.
 - 3. MM Systems Corporation
 - 4. Watson Bowman Acme, BASF Corp.
 - 5. Nystrom Building Products
 - 6. Architectural Art Mfg. Division, Pittcon Architectural Metals, LLC
 - 7. Jointmaster by Inpro Corp.
- B. Products of other manufacturers will be considered for acceptance provided they equal or exceed the material requirements and functional qualities of the specified product. The "Substitution Request Form" and complete technical data for evaluation must accompany request for A/E's approval. All materials for evaluation must be received by the Project Manager and Specification Department at least 10 days prior to bid due date. Additional approved manufacturers will be issued by Addendum.

2.2 SYSTEM DESCRIPTION

- A. General: Provide expansion control systems of design, basic profile, materials, and operation indicated. Provide units with capability to accommodate variations in adjacent surfaces.
 - 1. Furnish units in longest practicable lengths to minimize field splicing. Install with hairline mitered corners where expansion control systems change direction or abut other materials.
 - 2. Include factory-fabricated closure materials and transitions pieces, T-joints, corners, curbs, cross-connections, and other accessories as required to provide continuous expansion control systems.
- B. Provide factory fabricated architectural joint systems capable of withstanding the types of loads and of accommodating the kinds of movement, and the other functions for which they are designed including those specified below, without failure. Types of failure include those listed in Appendix X3 of ASTM E1399.
 - 1. Joints in Fire Resistance Rated Assemblies: Maintain fire resistance ratings of assemblies.
 - 2. Joints in Smoke Barriers: Maintain integrity of smoke barrier.
 - 3. Other Joints: Where indicated, provide joint systems that prevent penetration of water, moisture, and other substances deleterious to building components or content.

2.3 MATERIALS

- A. Aluminum: ASTM B 221, Alloy 6063-T5 for extrusions; ASTM B 209, Alloy 6061-T6 for sheet and plate.
 - 1. Apply manufacturer's standard protective coating on aluminum surfaces to be placed in contact with cementitious materials.
 - 2. Class II, Clear Anodic Finish: AA-M12C22A31 (Mechanical Finish: nonspecular as fabricated; Chemical Finish: etched, medium matte; Anodic Coating: Architectural Class II, clear coating 0.010 mm or thicker) complying with AAMA 611.
- B. Elastomeric Seals: Manufacturer's standard preformed elastomeric membranes or extrusions to be installed in metal frames.
- C. Non-Metallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, non-metallic aggregate grout, noncorrosive nonstaining, mixed with water to consistency suitable for application and a 30 minute working time.

- D. Accessories:
 - 1. Manufacturer's standard anchors, clips, fasteners, set screws, spacers, and other accessories compatible with material in contact, as indicated or required for complete installations.
- 2.4 ARCHITECTURAL JOINT SYSTEMS, GENERAL
 - A. Design Criteria:
 - 1. Nominal Joint Width: As indicated.
- 2.5 FLOOR EXPANSION JOINT COVERS
 - A. Metal-Plate Floor Joint Cover (Gym/Stage Threshold/Transition): Metal cover plate fixed on one side of joint gap and free to slide on other.
 - 1. Manufacturers: Subject to compliance with requirements; provide one of the following:
 - a. GYMF; C/S Systems.
 - b. GF-2P (Gym Floor Cover); Balco.
 - c. SP-2-2; MM Systems.
 - d. Model FJF; Watson Bowman Acme.
 - e. DT-6; Nystrom Building Products.
 - f. K-15-11-11 (K-Series); Architectural Art Mfg., Inc.
 - g. 801-A01; Jointmaster/Inpro.
 - 2. Application: Floor to floor.
 - 3. Installation: Surface mounted.
 - 4. Load Capacity:
 - a. Uniform Load: 50 lb/sq. ft.
 - b. Concentrated Load: 300 lb.
 - c. Maximum Deflection: 0.0625 inch.
 - 5. Cover-Plate Design: Plain.
 - 6. Exposed Metal:
 - a. Aluminum: Clear anodic, Class I, unless otherwise noted.
- 2.6 WALL EXPANSION JOINT COVERS
 - A. Metal-Plate Wall Joint Cover: Metal cover plate fixed on one side of joint gap and free to slide on other.
 - 1. Manufacturers: Subject to compliance with requirements; provide one of the following:
 - a. ASM Series; C/S Systems.
 - b. WD Series; Balco.
 - c. EX-K Systems; MM Systems.
 - d. Wabo Fastwall EWH; Watson Bowman Acme Corp.
 - e. WJ Series; Nystrom Building Products.
 - f. GXX-59-14; Architectural Art Manufacturing, Inc.
 - g. 811 Series; InPro Corporation.
 - 2. Application: Wall to wall and wall to wall corner.
 - 3. Exposed Metal:
 - a. Aluminum: Clear anodic, Class I.

2.7 FABRICATION

A. Provide expansion joint cover assemblies of design, basic profile, materials, and operation indicated. Select units comparable to those indicated or required to accommodate joint size, variations in adjacent surfaces, and structural movement. Furnish units in longest practicable lengths to minimize number of end joints. Provide hairline mitered corners where joint changes directions or abuts other materials. Include closure materials and transition pieces, tee-joints, corners, cross-connections, and other accessories as required to provide continuous joint cover assemblies.

2.8 FINISHES

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable.

2.9 ALUMINUM FINISHES

A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces where architectural joint systems will be installed for installation tolerances and other conditions affecting performance of work.
- B. Notify A/E where discrepancies occur that will affect proper expansion joint cover assembly installation and performance.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Prepare substrates according to architectural joint system manufacturer's written instructions.
- B. Coordinate and furnish anchorages, setting drawings, and instructions for installing expansion joint cover assemblies. Provide fasteners of metal, type, and size to suit type of construction indicated and to provide for secure attachment of expansion joint cover assemblies.

3.3 INSTALLATION

- A. Comply with manufacturer's written instructions for storing, handling, and installing architectural joint assemblies and materials unless more stringent requirements are indicated.
- B. Metal Frames: Perform cutting, drilling, and fitting required to install joint systems.
 - 1. Install in true alignment and proper relationship to joints and adjoining finished surfaces measured from established lines and levels.
 - 2. Adjust for differences between actual structural gap and nominal design gap due to ambient temperature at time of installation. Notify A/E where discrepancies occur that will affect proper joint installation and performance.
 - 3. Cut and fit ends to accommodate thermal expansion and contraction of metal without buckling of frames.
 - 4. Repair or grout blockout as required for continuous frame support using nonmetallic, shrinkage-resistant grout.
 - 5. Locate in continuous contact with adjacent surfaces.
 - a. Standard-Duty Systems: Shim to level where required. Support underside of frames continuously to prevent vertical deflection when in service.
 - 6. Locate anchors at interval recommended by manufacturer, but not less than 3 inches from each end and not more than 24 inches o.c.
- C. Install with hairline mitered corners where expansion joint cover assemblies change direction or abut other materials.

D. Terminate exposed ends of expansion joint cover assemblies with field- or factory-fabricated termination devices.

3.4 PROTECTION

- A. Do not remove protective covering until finish work in adjacent areas is complete. When protective covering is removed, clean exposed metal surfaces to comply with manufacturer's written instructions.
- B. Protect the installation from damage by work of other Sections. Where necessary due to heavy construction traffic, remove and properly store cover plates or seals and install temporary protection over joints. Reinstall cover plates or seals prior to Substantial Completion of the Work.

END OF SECTION 07 95 13.13

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes furnishing and installation of:
 - 1. Cabinets for automatic external defibrillators (AEDs).
 - 2. Automatic external defibrillators.
- B. Related Requirements:
 - 1. Division 10 Section "Fire Extinguisher Cabinets."

1.2 REFERENCES

- A. Reference Standards: The publications listed below form a part of this Section to the extent referenced. The publications are referred to within the text by the basic designation only.
 - 1. American Heart Association (AHA): 2005 American Heart Association Guidelines for Cardiopulmonary Resuscitation and Emergency Cardiovascular Care.

1.3 ADMINISTRATIVE REQUIREMENTS

- A. Sequencing:
 - 1. Comply with defibrillator cabinet manufacturer's written recommendations for sequencing construction operations.
 - 2. Comply with manufacturer's ordering instructions and lead time requirements to avoid construction delays.
- B. Coordination
 - 1. Coordinate size of automated external defibrillator cabinets to ensure that type and capacity of automated external defibrillators indicated are accommodated.
 - 2. Coordinate sizes and locations of automated external defibrillator cabinets with wall depths.

1.4 ACTION SUBMITTALS

- A. Product Data: For specified products:
 - 1. Cabinets: Materials description for defibrillator cabinets include roughing-in dimensions, details showing mounting methods, relationships to surrounding construction, door hardware, cabinet type and materials, trim style and door construction, door style and materials.
 - 2. Installation instructions for each product specified.

1.5 CLOSEOUT SUBMITTALS:

- A. General: Closeout Submittals are to be submitted with O and M Manuals only. Do not submit with other ACTION and INFORMATIONAL Submittals:
 - 1. Operation and Maintenance Data: For installed products. Include manufacturer's instructions covering maintenance requirements.

1.6 QUALITY ASSURANCE

- A. Qualifications:
 - 1. Manufacturer Qualifications: Manufacturer capable of providing field service representation during construction and approving application method.
 - 2. Installer: Experienced in performing work of this Section who has specialized in assembly and installation of work similar to that required for this Project.

B. Single-Source Responsibility: Provide both defibrillator cabinet and alarm mechanism from a single manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Delivery and Acceptance Requirements: Deliver materials in manufacturer's original packaging with identification labels intact.
- B. Storage and Handling Requirements: Store materials protected from exposure to harmful weather conditions and at temperature conditions recommended by manufacturer.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Cabinet Products: Subject to compliance with requirements, select from one of the following.
 - 1. Lifestart 1400 Series by JL Industries Division, Activar Construction Products Group.
 - 2. 180 Series by Modern Metal Products Division of Technico Inc.
 - 3. PFE7023D by Philips Healthcare Division of Royal Philips Electronics N.V.
- B. Defibrillators: Select from one of the following:
 - 1. Powerheart AED G3 Plus by Cardiac Science, Opto Cardiac Care Ltd.
 - 2. HeartStart OnSite (HS1) AED by Philips Healthcare Div'n of Royal Philips Electronics N.V.
 - 3. Medtronic LifePak CR Plus AED by Physio-Control Inc.
 - 4. AED Plus by ZOLL Medical Div'n of Asahi Kasei Corp.
- C. Products of other manufacturers will be considered for acceptance provided they equal or exceed the material requirements and functional qualities of the specified product. Requests for A/E's approval must be accompanied by the "Substitution Request Form" and complete technical data for evaluation. All materials for evaluation must be received by the Project Manager and Specification Department at least ten days prior to bid due date. Additional approved manufacturers will be issued by Addendum.
- 2.2 CABINETS FOR AUTOMATIC EXTERNAL DEFIBRILLATORS (AEDs)
 - A. Cabinet with Steel Trim and Door:
 - 1. Cabinet Style: Semi-recessed.
 - 2. Components:
 - a. Tub: Cold-rolled steel.
 - 1) Finish: Factory-applied powder coat paint finish.
 - a) Standard Color: White.
 - b. Door and Trim Construction: Cold-rolled steel; flush doors with 5/8 inch door stop attached by continuous hinge and equipped with zinc-plated with roller catch.
 - 1) Finish: Factory-applied powder coat paint finish.
 - a) Standard Color: White.
 - 2) Door Style:
 - a) Full Tempered Glazing; Pull & AED Decal
 - c. Trim Style and Depth:
 - 2) Semi-Recessed Cabinet:
 - a) Rolled Edge: 3 inch.
 - 4) Trim Dimensions: 1-3/4 inch face trim on door and frame.
 - 4. Alarms: Standard: 85 db Commander (audible) cabinet-mounted alarm standard (battery operated) to protect against theft or tampering. Alarm deactivated when door is closed.
 - 5. Wall Signs and Cabinet Lettering:
 - a. AED wall signs.

2.3 AUTOMATED EXTERNAL DEFIBRILLATOR (AED)

- A. Automated External Defibrillator: Portable automated external defibrillator capable of automatically diagnosing life-threatening cardiac arrhythmias, suitable for use on adult or pediatric patients. Lid release on/off button operation. Type, size, and capacity for each cabinet indicated.
 - 1. Basis-of-Design Product: Subject to compliance with requirements, provide Activar Construction Products Group, Inc. JL Industries; LIFEPAK CR2 Defibrillator or comparable product.
 - 2. Battery Capacity: 13 hours.
 - 3. Standby Life: 6 years.
 - 4. Accessories: Pediatric Pad-Pak.

2.4 ACCESSORIES

A. Cabinet seals or pull seals (to monitor if AED has been accessed or handled).

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Site Verification of Conditions:
 - 1. Prior to installation of defibrillator cabinets, verify that substrates previously installed under other sections or contracts are acceptable for product installation in accordance with manufacturer's instructions.
 - 2. Examine conditions affecting performance of work, with Installer present, for compliance with requirements and other conditions.
 - 3. Inform A/E of unacceptable conditions immediately upon discovery.
 - 4. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Comply with manufacturer's Product Data and written installation instructions applicable to products and applications indicated, including product technical bulletins, product catalog installation instructions, and product carton installation instructions to comply with applicable regulations.
- B. Automated External Defibrillator Cabinets: 48 inches above finished floor to top of defibrillator.
- C. Automated External Defibrillator Cabinets: Fasten cabinets to structure, square and plumb.
 1. Fasten mounting brackets to inside surface of automated external defibrillator cabinets, square and plumb.
- D. Identification
 - 1. Apply decals or vinyl lettering at locations indicated.

3.3 ADJUSTING

- A. Adjust defibrillator cabinet doors to achieve smooth operation.
- 3.4 CLEANING
 - A. Upon completing installation, remove surplus and excess materials, rubbish, tools, and equipment.

3.5 CLOSEOUT ACTIVITIES

A. Demonstration:

- 1. Instruct Owner's designated maintenance personnel in care, adjustment, and operation of defibrillator cabinets.
- 2. Forward statement to A/E countersigned by maintenance personnel confirming that these instructions have been provided.

3.6 PROTECTION

A. Protect installed products from damage during construction.

END OF SECTION 10 43 13

SUBSURFACE INVESTIGATION & GEOTECHNICAL RECOMMENDATIONS

ZIONSVILLE HIGH SCHOOL LOCKER ROOM ZIONSVILLE, INDIANA A&W PROJECT NO.: 24IN0394

PREPARED FOR: TLF, INC. INDIANAPOLIS, INDIANA

PREPARED BY: ALT & WITZIG ENGINEERING, INC. GEOTECHNICAL DIVISION

AUGUST 7, 2024

Alt & Witzig Engineering, Inc.



4105 West 99th Street • Carmel, Indiana • 46032 Ph (317) 875-7000 • Fax (800) 875-6028

August 7, 2024

TLF, Inc. 3901 West 86th Street, Suite 200 Indianapolis, Indiana 46268 Attn: Ms. Tracy Chariton

Report of Subsurface Investigation and Geotechnical Recommendations

RE: Zionville High School Locker Room 1000 Mulberry Street Zionsville, Indiana *Alt & Witzig File: 24IN0394*

Dear Ms. Chariton:

In compliance with your request, we have conducted a subsurface investigation and geotechnical evaluation for the above referenced project. It is our pleasure to transmit an electronic copy of the report.

The purpose of this subsurface investigation was to determine the various soil profile components, the engineering characteristics of the subsurface materials, and to provide criteria for use by the design engineers in assessing the site for construction, preparation of site grading plans, and determination of appropriate foundation types. A detailed discussion of our subsurface investigation results and recommendations are presented herein.

We appreciated the opportunity to work with you on this project. Often, because of design and construction details that occur on a project, questions arise concerning the soil conditions. If we can give further service in these matters, please contact us at your convenience.



Sincerely, *Alt & Witzig Engineering, Inc.*

licholas tom

Nicholas K. Hayes, E.I.

Thomas J. Coffey, P.E.

Subsurface Investigation and Foundation Engineering Construction Materials Testing and Inspection Environmental Services



TABLE OF CONTENTS

INTRODUCTION	1
DESCRIPTION OF SITE	2
FIELD INVESTIGATION	5
LABORATORY INVESTIGATION	7
SUBSURFACE CONDITIONS	8
GEOTECHNICAL ANALYSIS AND RECOMMENDATIONS1	0
CONSTRUCTION CONSIDERATIONS	6
STATEMENT OF LIMITATIONS	8

APPENDIX A

Recommended Specifications for Compacted Fills and Backfills Undercut Detail for Footing Excavation in Unstable Materials Boring Location Plan Boring Logs General Notes

APPENDIX B

Seismic Design Parameters Custom Soil Resource Report for Boone County, Indiana



INTRODUCTION

This report presents the results of a subsurface investigation performed for the proposed additions to Zionsville High School in Zionsville, Indiana. Our investigation was conducted for TLF, Inc. of Indianapolis, Indiana. Authorization to perform this investigation was in the form of a proposal prepared by Alt & Witzig, Engineering, Inc. (Alt & Witzig Proposal: 2406G007) that was authorized by a representative of the client.

The scope of this investigation included a review of geological maps of the area and a review of geologic and related literature, a reconnaissance of the immediate site, a subsurface exploration, field and laboratory testing, and engineering analysis and evaluation of the materials.

The purpose of this subsurface investigation was to determine the various soils profile components, the engineering characteristics of the subsurface materials, and to provide criteria for use in assessing the site for construction and evaluating subsurface conditions.

The scope or purpose of this investigation did not either specifically or by implication provide an environmental assessment of the site.



DESCRIPTION OF SITE

The site is located at Zionsville High School, at the street address of 1000 Mulberry Street in Zionsville, Indiana. The proposed building addition is to be constructed on the south side of the school, immediately east of the aquatics center. An aerial photograph of the site taken in 2022 is provided in *Exhibit 1* below.



Exhibit 1 – 2022 Aerial Photograph of Site; Google Earth

Site Description

The proposed building addition area is relatively flat, with an estimated elevation difference of one (1) foot across the proposed area, with elevations ranging between 901 feet to 902 feet per Google Earth. Ground cover across the site during drilling operations consisted of grass, landscaping, asphalt pavement, and concrete sidewalks. The immediate surrounding areas are developed with Zionsville High School, along with associated infrastructure and sporting fields.



Site History

Based on a review of historical aerial photographs, it appears that earthwork was conducted south of the proposed building addition, as shown in *Exhibit 2* below. It is understood that a new driving lane and roundabout will be constructed in this area.

Exhibit 2 – 2010 Aerial Photograph of Site; Google Earth





Exhibit 3 – 2012 Aerial Photograph of Site; Google Earth

Exhibit 4 – 2014 Aerial Photograph of Site; Google Earth





FIELD INVESTIGATION

Boring Locations

Field investigations to determine the engineering characteristics of the subsurface materials included a reconnaissance of the project site and performing five (5) soil borings, at locations selected by the client, located approximately as shown on the *Boring Location Plan*, performing standard penetration tests, and obtaining soil samples retained in the standard spilt-spoon sampler for further laboratory testing. The apparent groundwater level at each boring location was also determined.

Drilling and Sampling Procedures

The soil borings were drilled using a truck-mounted drilling rig equipped with a rotary head. Hollowstem augers were used to advance the holes. The advancement of the borings was temporarily stopped at regular intervals in order to perform standard penetration tests in accordance with ASTM Procedure D-1586 to obtain the standard penetration value of the soil.

The standard penetration test involves driving a split spoon soil sampler into the ground by dropping a 140-pound hammer, thirty (30) inches. The number of hammer drops required to advance the split-spoon sampler one (1) foot into the soil is defined as the standard penetration value. The soil samples retained in the split-spoon sampling device as a result of the penetration tests were obtained, classified, and labeled for further laboratory investigation.

Water Level Measurements

The apparent groundwater level at each boring location was measured during and upon completion of the drilling operations.

These water level measurements consisted of observing the depth at which water was encountered on the drilling rods during the soil sampling procedure and measuring the depth to the top of any water following removal of the hollow stem augers. It should be noted that the groundwater level measurements recorded on the individual *Boring Logs* in Appendix A of this report are accurate only for the specific dates on which the measurements were performed. It must be understood that the groundwater levels will fluctuate throughout the year and the *Boring Logs* do not indicate these fluctuations.



Ground Surface Elevation

Ground surface elevations were not available at the time of this report. However, available topographic information provided by Google Earth indicates that the proposed addition area varies in elevation from approximately 901 to 902 feet.



LABORATORY INVESTIGATION

In addition to field investigations, a supplemental laboratory investigation was conducted to ascertain additional pertinent engineering characteristics of the subsurface materials. The laboratory-testing program included:

- Classification of soils in general accordance with ASTM D-2488
- Moisture content tests in general accordance with ASTM D-2216
- Samples of the cohesive soil were frequently tested in unconfined compression by use of a calibrated spring testing machine.
- A soil Penetrometer was used as an aid in determining the strength of the soil.

The values of the unconfined compressive strength as determined on soil samples from the split-spoon sampling must be considered, recognizing the manner in which they were obtained since the split-spoon sampling techniques provide a representative but somewhat disturbed soil sample.



SUBSURFACE CONDITIONS

General

The types of foundation materials encountered have been visually classified and are described in detail on the *Boring Logs*. The results of the field penetration tests, strength tests, water level observations and laboratory water contents are presented on the *Boring Logs* in numerical form. Representative samples of the soils encountered in the field were placed in sample jars and are now stored in our laboratory for further analysis if desired. Unless notified to the contrary, all samples will be disposed of after two (2) months.

Soil Conditions

The borings conducted in the grass areas encountered approximately two (2) to five (5) inches of topsoil at the ground surface. Boring B-03, conducted in the asphalt pavement, encountered approximately three (3) inches of asphalt underlain by twelve (12) inches of crushed stone at the ground surface.

Beneath the surface materials, borings B-01, B-02, and B-04 encountered fill materials consisting of cohesive and granular soils to depths ranging from four (4) to eleven (11) feet. It should be noted that boring B-01 encountered brick debris within the soil layer between nine (9) and eleven (11) feet. The soils then transitioned to medium stiff to stiff cohesive soils to the termination depths of the borings. Boring B-01 encountered a soft layer of cohesive soil at a depth of twenty-one (21) feet. Also, boring B-02 encountered a layer of medium dense granular soil at a depth of seventeen (17) to twenty-one (21) feet.

Detailed soil descriptions at each boring location have been included on the *Boring Logs* in Appendix A of this report.

According to the *Soil Survey of Boone County, Indiana* published by the United States Department of Agriculture Soil Conservation Service, the majority of the shallow soil covering this site is classified as Crosby-Urban land-Treaty complex (YctA) and Miami silt loam-Urban land complex (YmsB2). The *Custom Soil Resource Report for Boone County, Indiana* has been included in Appendix B.



Bedrock Geology

Geologic maps published by the Indiana Geological Survey indicate the bedrock at this site consists of the New Albany Group, which is characterized by shale, dolomite, and sandstone of the Devonian/Mississippian age. The approximate elevation of this bedrock is mapped to be 700 feet, which is estimated to be greater than 100 feet of the existing ground surface.

Seismic Design Considerations

Based on the field and laboratory tests performed on the subsurface materials and an assumption that the bedrock surface is greater than 100 feet below the existing ground surface, this site should be considered a Site Class D in accordance with the current Indiana Building Code.

The location of the site was entered into the website <u>www.seismicmaps.org</u> to determine seismic parameters. Maximum spectral response acceleration values of Ss=0.152 and $S_1=0.083$ g were generated by the program. Additional parameters are included in the printout in Appendix B.

Groundwater

Groundwater levels taken during and upon completion of the boring operations yielded measurements greater than eight (8) feet below the ground surface. The exact location of the water table may fluctuate somewhat depending upon normal seasonal variations in precipitation and surface runoff.

The *Soil Survey of Boone County, Indiana* indicates a seasonal high groundwater table as shallow as six (6) inches below the natural ground surface. Again, it should be noted that the groundwater level measurements recorded on the individual *Boring Logs* included in Appendix B of this report, are accurate <u>only</u> for the dates on which the measurements were performed.



GEOTECHNICAL ANALYSIS & RECOMMENDATIONS

Project Description

It is anticipated that the proposed addition will be two-story, slab-on-grade addition, constructed on south ends of the existing building. Also, a new driving lane and roundabout will be constructed south of the proposed addition. The location of the soil borings in relation to the layout of the site is shown on the enclosed *Boring Location Plan*.

Grading plans were not available at the time of this report. It is assumed that finished grade will match the existing structure. Based on the existing topography of the site, approximately one (1) foot of relief exists across the footprint of the proposed addition.

It is assumed that structural loads for the building addition will be transferred to the soils by spread footings and continuous wall footings founded at a shallow depth, if possible. Maximum column loads of 100 kips and wall loads of 6 klf were provided by TLF, Inc.

Existing Structure/Utility Concerns

As previously mentioned, the Zionsville High School Building occupies the site. Also, a small building occupies the location of the proposed driving lane and roundabout. It is understood that the small building will be demolished and removed. Shallow, uncontrolled fills should be anticipated from activities associated with past construction. Care should be taken to properly abandon any existing utilities located in the area of the addition. At no time should new foundations be placed on or above abandoned utilities, old floor slabs, or foundations.

Upon completion of the demolition process, it is recommended that Alt & Witzig Engineering, Inc. evaluate the soil conditions in the area of the previous structure prior to backfilling. It is further recommended that if backfilling is required, a representative of Alt & Witzig Engineering, Inc. be present to assure that proper compaction is achieved.

Adjacent Foundations

New foundations to be placed near or adjacent to existing foundations should be constructed such that undermining of adjacent footings and lateral loading of footings located at a different elevation is



avoided. If it is necessary to construct the new foundations within the "influence area" of the existing structure, shoring or underpinning of the existing structure will be necessary to allow for construction. The lateral loads applied by the existing footing should be considered in design of the proposed foundation. This investigation did not include the evaluation of the existing structure or foundation system. Caution must be exercised during construction to not undermine existing foundations or jeopardize the integrity of the existing structure.

Foundation Recommendations

Considering the encountered soil conditions at the boring locations, the estimated loads of the structure, and the relative economics of the available foundation types, conventional spread and continuous wall footings were considered, as well as helical piers.

Conventional Footings

As mentioned, borings B-01, B-02, and B-04 encountered fill materials to depths of four (4) to eleven (11) feet. Due to the uncontrolled nature of the fill materials, it is recommended that these materials be undercut to firm natural soils.

Net allowable bearing pressures of **2,500** and **2,000 psf** are recommended for dimensioning spread footings and continuous wall footings, respectively, provided they are founded on firm natural soil or properly compacted structural fill.

Wherever unsuitable materials are encountered, these footing areas should be undercut to firm natural soils to minimize potential settlement. Since the site limitation do not appear to allow for widening of potential footing excavations to accommodate compacted structural fill in the areas of the undercut, it is recommended that, if it is not desired to extend the footings to this depth, the original bottom of footing elevation may be reestablished using lean concrete. Care must be taken to undercut and reestablish the footing elevation in accordance with the *Undercut Detail for Footing Excavation in Unstable Materials* diagram in Appendix A of the report.

It is recommended that a representative of Alt & Witzig Engineering, Inc. inspect all foundation excavations prior to the placement of concrete. At the time of this inspection, Housel penetrometer or other approved tests may be performed in order to confirm that suitable materials are present.



Helical Piers

Due to the depth and nature of the fill materials, particularly in boring B-01, we have also considered helical piers as an option for the foundation system. Helical piers will also be advantageous to avoid overlapping loads from the existing footings and the new footings as well.

Helical piers utilize a central bar or pipe outfitted with a helical auger on the end that is rotated into the ground to a specified depth. The piers can accept loading immediately upon installation and are typically installed by either a backhoe or bobcat-mounted equipment.

The capacity of the helical piers depends on the size of the helix selected and the depth into the firm underlying soils that the piers are installed. Typically, individual working pier capacities in the range of 30 to 80 kips are feasible. Higher capacities may be available as well. The capacity of each individual pier may be determined at the time of installation through real-time monitoring measurements. It is recommended that as a minimum the piers be extended to the stiff cohesive soils encountered approximately fourteen and one-half (14½) feet below the existing ground surface. The depth and capacity of the piers should be designed by the specialty contractor.

General

The above recommended bearing pressures will help reduce differential settlements associated with footings founded on soil with varying stiffness across the building pad. Using the above-mentioned bearing pressure and recommendations for limiting settlements, total settlements of less than one (1) inch and differential settlements of one half ($\frac{1}{2}$) inch or less can be anticipated. In utilizing the above-mentioned net allowable pressures for dimensioning footings, it is necessary to consider only those loads applied above the finished floor elevation.

In order to alleviate the effects of seasonal variation in moisture content on the behavior of the footings and eliminate the effects of frost action, all exterior foundations should be founded a minimum of three (3) feet below the final grade.

Some modifications to the recommendations provided in this report may be necessary based on potential complications or modifications to the design plan. The modifications may influence the overall cost of the project and construction sequence. If complications become apparent to the design


team or owner, this information should be provided to Alt & Witzig Engineering, Inc. at the earliest possible date.

Floor Slab Recommendations

It is typically desirable to place the floor slab as a slab-on-grade supported by the soil. In the areas where the existing grade is above the final floor elevation, the building area should be undercut and a well-draining granular material placed beneath the slab. In those areas where the existing grade is below the final floor elevation, a well-compacted structural fill will be necessary to raise the site to the desired grade. All fill materials may consist of approved materials if proper moisture content and compaction procedures are maintained.

Prior to elevating the site, all topsoil should be stripped from the site. The subgrade soils must then be proofrolled with approved equipment. It is recommended that a representative of Alt & Witzig Engineering, Inc. be present to determine the exact depth of undercutting and to monitor backfilling operations if necessary. Areas of shallow unstable materials should be anticipated in most areas due to the encountered fill materials. The exact remediation method used will be dependent upon the size of the area and the types of materials encountered, as well as the project schedule. If weather conditions are favorable, the soils may be aerated, dried, and recompacted or undercut and replaced. Remediation will be dictated by the field conditions upon construction.

After the building area has been raised to the proper elevation, a layer of well-draining granular material should be placed immediately beneath all floor slabs. It is recommended that the materials within the subgrade area, above footing elevation, be compacted to a minimum density of 93 percent of maximum density in accordance with ASTM D-1557.

A modulus of subgrade reaction, k_{30} , of 75 pci is recommended for the shallow cohesive soils and fill materials. It should be noted that the fill materials may require some remediation prior to utilizing the 75 pci modulus of subgrade reaction.

Pavement Recommendations

The strength of the subgrade soils at this site depends upon several variables including compaction and drainage. It is, therefore, extremely important that all paved areas be designed to prevent water from collecting or ponding immediately beneath the pavement. This can be accomplished by sheet



draining the parking area and sloping the subgrade soils and outletting them to a drain or a ditch to allow for subgrade drainage, or by the installation of a subsurface drainage system. It is recommended that underdrains be installed at the transitions from concrete to asphalt as well.

For these soils to provide adequate support for pavement, it will also be necessary that the earthmoving contractor follow proper site work techniques. The exposed subgrade should be proof-rolled with equipment approved by a representative of Alt & Witzig Engineering, Inc. This proof-rolling will assist in identifying pockets of soft unstable materials beneath exposed subgrades. As mentioned before, an existing building is located in the area of the new driving lane and roundabout. It is recommended that upon completion of the demolition process, it is recommended that Alt & Witzig Engineering, Inc. evaluate the soil conditions in the area of the previous structure prior to backfilling. It is further recommended that if backfilling is required, a representative of Alt & Witzig Engineering, Inc. be present to assure that proper compaction is achieved.

In areas where fill will be required to raise the site to proposed grade, the performance of the pavements will be greatly affected by the quality of compaction achieved in the subgrade soils. Thus, it is recommended that all pavement areas be compacted to 93 percent of the material's maximum dry density as determined by ASTM D-1557.

Lateral Earth Pressures on Subsurface Walls

The amount of pressure exerted by the backfill on the walls will depend on the height of the wall, drainage provisions, type of backfill, method of placing the backfill, and the proximity of nearby shallow foundations. The free draining material should be placed behind the wall and include an area on a 1:1 slope from the heel of the wall up to the ground surface.

It is recommended that the material used as backfill consist of clean sand and gravel containing less than five (5) percent fines by weight. A representative of Alt & Witzig Engineering, Inc. should inspect this material to determine its suitability. It is recommended that the granular backfill immediately adjacent to the wall be placed with a moderate amount of tamping and compacting.

The lateral earth pressure will be minimized if the backfill is a clean granular material, and if the backfill is placed with a minimum amount of tamping. For design purposes, it is recommended that coefficient of at rest earth pressure (k_0) of 0.5 be used for structurally designing subsurface



walls where minimal compactive effort can be used on the backfill. Also, an active coefficient (k_a) of 0.3 and passive earth coefficient (k_o) of 3.3 should be considered.

Assuming the unit weight of the backfill is 125 pcf, a $k_0 = 0.5$ would correspond to an equivalent fluid pressure of 63 pcf per foot of wall height. This equivalent fluid pressure would increase linearly from 0 psf at ground surface to a maximum at the bottom of the footing. Please note that the above pressures are applicable during a fully drained condition.



CONSTRUCTION CONSIDERATIONS

Site Preparation

Excessively organic topsoil and loose dumped fill materials will generally undergo high volume changes that are detrimental to the behavior of pavements, floor slabs, structural fills, and foundations placed upon them. It is recommended that all topsoil and/or loose materials be stripped from the construction areas and wasted or stockpiled for later use.

The depth and consistency of these materials will vary across the site. It should be noted that the soil borings only indicate the apparent topsoil and asphalt pavement thickness at their specific locations. Borings do not indicate variations in the thickness of these layers between selected locations. Thus, borings only provide a general indication of the amount of stripping.

The condition of the subgrade at the time of earthmoving operations and the methods used by the contractor will influence the depth of stripping. A representative of Alt & Witzig Engineering, Inc. in the field should determine the exact depth of stripping and undercutting at the time of stripping operations.

It is recommended that after the above-mentioned stripping procedures have been performed, the exposed subgrade should be proofrolled with approved equipment. This proofrolling will determine where areas of soft unsuitable materials are encountered. Due to the encountered fill materials, it is anticipated that some subgrade soils will not favorably pass a proofroll inspection. It is recommended that a representative of Alt & Witzig Engineering, Inc. be present for this phase of this project.

After the existing subgrade soils are excavated to design grade, proper control of subgrade compaction and fill, and structural fill replacement should be maintained in accordance with the *Recommended Specifications for Compacted Fills and Backfills*, presented in Appendix A of this report; thus minimizing volume changes and differential settlements which are detrimental to behavior of shallow foundations, floor slabs, and pavements.

Groundwater

Depending upon the time of the year and the weather conditions when the excavations are made, seepage from surface runoff may occur into shallow excavations or soften the subgrade soils. Since



these foundation materials tend to loosen when exposed to free water, every effort should be made to keep the excavations dry should water be encountered. Sump pumps or other conventional dewatering procedures should be sufficient for this purpose within the cohesive soils.

It is also recommended that all concrete for footings be poured the same day the excavation is made.



STATEMENT OF LIMITATIONS

This report is solely for the use of TLF, Inc. and any reliance of this report by third parties shall be at such party's sole risk and may not contain sufficient information for purposes of other parties for other uses. This report shall only be presented in full and may not be used to support any other objectives than those set out in the scope of work, except where written approval and consent are provided by TLF, Inc. and Alt & Witzig Engineering, Inc.

An inherent limitation of any geotechnical engineering study is that conclusions must be drawn based on data collected at a limited number of discrete locations. The geotechnical parameters provided in this report were developed from the information obtained from the test borings that depict subsurface conditions only at these specific locations and on the date indicated on the boring logs. Soil conditions at other locations may differ from conditions encountered at these boring locations and groundwater levels shall be expected to vary with time. The nature and extent of variations between the borings may not become evident until the course of construction.

The exploration and analysis reported herein is considered in sufficient detail and scope to form a reasonable basis for design. The recommendations submitted are based on the available soil information and assumed design details enumerated in this report. If actual design details differ from those specified in this report, this information should be brought to the attention of Alt & Witzig Engineering, Inc. so that it may be determined if changes in the foundation recommendations are required.



APPENDIX A

Recommended Specifications for Compacted Fills and Backfills Undercut Detail for Footing Excavation in Unstable Materials Boring Location Plan Boring Logs General Notes



RECOMMENDED SPECIFICATIONS FOR COMPACTED FILLS AND BACKFILLS

All fill shall be formed from material free of vegetable matter, rubbish, large rock, and other deleterious material. Prior to placement of fill, a sample of the proposed fill material should be submitted to Alt & Witzig Engineering, Inc. for approval. The surface of each layer will be approximately horizontal but will be provided with sufficient longitudinal and transverse slope to provide for runoff of surface water from every point. The fill material should be placed in layers not to exceed eight (8) inches in loose thickness. Each layer should be uniformly compacted by means of suitable equipment of the type required by the materials composing the fill. Under no circumstances should a bulldozer or similar tracked vehicles be used as compacting equipment. Material containing an excess of water so the specified compaction limits cannot be attained should be spread and dried to a moisture content that will permit proper compaction. The addition of water may be required if the fill is below moisture content that will permit compaction. All fill should be compacted to the specified percent of the maximum density obtained in accordance with ASTM density Test D-1557 (95 percent of maximum dry density below the base of footing elevation, 93 percent of maximum dry density beneath floor slabs and pavements). Should the results of the in-place density tests indicate that the specified compaction limits are not obtained; the areas represented by such tests should be reworked and retested as required until the specified limits are reached.

UNDERCUT EXCAVATION FOR ISOLATED FOOTINGS IN UNSTABLE MATERIALS







CLIENT TLF, Inc	D						_	BOF	RING	G#_		<u>B</u> -0	1	
PROJECT NAME	Zionsville Hig	h School Locker Ro	oom Ado	dition			_	ALT	& V	VITZIG	FILE #	24IN	10394	
PROJECT LOCATIC	N Zionsvill	e, IN					_							
		SAMPLING INFORMAT	IION											
Date Started	7/25/24	Hammer Wt	14	ID Ibs	5.									
Date Completed	7/25/24	Hammer Drop	3	<u>30</u> in.							TE	ST DA	TA	
Boring Method	HSA	Spoon Sampler O	D	<u>2</u> in.										
Driller <u>C. Pete</u>	erman	Rig Type <u>_D-50_I</u>	rack Al	<u>v</u>			d)	aphics aphics	er	netration ws/foot	nfined e Strength	etrometer	itent % ight (pcf)	
STRATA	SOIL CL	ASSIFICATION			_	<u>e</u>	le Type	ler Gra /ery Gr	nd Wate	ard Pe N - blov	f Uncor	f et Pene	ire Cor hit We	irks
ELEV.	SURFA	CE ELEVATION		Strata Depth	Depth Scale	samp No.	Samp	Samp Recov	Groun	Stand Test, I	Qu-tsf Comp	PP-tsf Pocke	Moistu Dry U	Rema
		TOPSOIL		0.2	-									
	Brov	wn Sandy CLAY				1	SS			11			12.5	
		(FILL)		4.0				Α						
					5 —	2	SS	X		3				
	Brown SAN	ND with a Trace of Clay				3	ss			3				
		(1722)		9.0				А						
	Brown Sand	dy Silty CLAY with Brick (FILL)	Г	11.0	10 -	4	SS	X		5				
					-									
					15 -	5	SS			13	43		11.2	
					-			Å						
	Gray	Sandy Silty CLAY			20 -	6	SS			4		0.5	14 7	
								А						
									0					
						_	~~			10				
				26.0	25 —	1	SS	Х		16		4.5	9.3	
	End o	f Boring at 26 feet												
Sample Typ	e			Grou	undwate	<u>r</u>		_	_			Boring	Metho	<u>d</u>
SS - Driven Split Sp ST - Pressed Shelby CA - Continuous Flig RC - Rock Core	oon y Tube ght Auger		 ○ During ▼ At Cor 	g Drillin npletio	g n	23	<u>3.0 ft</u> ft	 		H C D N	ISA - H IFA - C IC - D ID - N	Iollow S Continuc Priving C Iud Drill	item Au ous Fligh Casing ling	gers nt Augers
CT - Continuous Tul	be												Pa	age 1 of 1



IENT TLF, In	IC.							BOF	RING	G #		B-0	2	
OJECT NAME _	Zionsville Hig	h School Locker Room	Additi	on				ALT	- & V	VITZIG	FILE <u>#</u>	241	10394	
OJECT LOCATI	ON Zionsvil	le, IN												
	DRILLING and	SAMPLING INFORMATION	I											
Date Started	7/25/24	Hammer Wt	140	lbs										
Date Completed	7/25/24	Hammer Drop	30	in.	•									
Boring Method	HSA	Spoon Sampler OD	2	in.							IE	SIDA		
Driller <u>C. Pe</u> t	terman	Rig Type D-50 Trac	k ATV	_						5	ال	5	Ð	
								iphics aphics	er	netratic ws/foot	nfined e Strenç	etromet	itent % ight (pc	
TRATA	SOIL C	LASSIFICATION	_	_	_	e	le Type	ler Gra verv Gr	nd Wate	lard Pe N - blov	f Uncor	f et Pene	ure Cor Init We	arks
ELEV.	SURFA	CE ELEVATION	Strata	Depth	Depth Scale	Samp No.	Samp	Samp Recov	Grour	Stand Test,	Qu-tst Comp	PP-tsI Pock∈	Moistu Dry U	Rema
		TOPSOIL	0).2										
	_					-								
	Brown	SAND and GRAVEL (FILL)			-	1	SS	X		34				
		. ,	4	1.0	•	-								
					5 -	2	ss	\square		11		3.0	11.8	
						-	-	Δ						
							00			10		0.0	44.5	
_					-	- 3	55	Х		10		2.0	11.5	
						-								
_	Brown	n Sandy Silty CLAY			10 -	4	ss	M		6		1.8	11.8	
						1	-	Д						
_						1								
					-									
			15	5.0	15 -	5	ss	∇		8	1.4		15.4	
	Grav	Sandy Silty CLAY				-	-	Д						
	0.2,		17	7.0										
	Grav Moist	Clavev SAND with Gravel												
	0.0,,				20 -	6	ss	∇		10				
			21	1.0		1	-	Λ						
	End o	or Boring at 21 feet												
Sample Ty	pe_ poon	∩ г	<u>.</u> Durina Dr	<u>ərou</u> illina	indwat n	er_	Drv f	t.		F	ISA - H	Boring	tem Aug	<u>a</u> gers
- Pressed Shell	by Tube	Ţ A	At Comple	etio	n		Dry f	t		C	FA - C	ontinuc	ous Fligh	t Augers
- Rock Core	.g. it / lager									N	1D - N	lud Dril	ling	



CLIENT TLF, In	С.							BOF		G #		B-0	3	
PROJECT NAME	Zionsville High	School Locker R	oom Additio	on				ALT	- & V	VITZIG	FILE #	± 24IN	10394	
PROJECT LOCATIO	ON Zionsville	e, IN												
Date Started	DRILLING and 7/25/24	SAMPLING INFORMA Hammer Wt	TION 140	lbs.										
Date Completed	<u>//25/24</u>	_ Hammer Drop _	30	in.							TE	ST DA	TA	
Boring Method		_ Spoon Sampler C	DD <u>2</u>	in.										
Driller <u>C. Pet</u>	erman	Rig Type <u>50_</u> _)e	aphics Braphics	iter	enetration ows/foot	onfined /e Strength	etrometer	ontent % eight (pcf)	
STRATA	SOIL CL	ASSIFICATION			_	e	le Tyj	ler Gr	aW br	ard P N - bl	f Unco	f et Pen	ire Co hit W	irks
ELEV.	SURFAC	E ELEVATION	Strata	Depth	Depth Scale	Samp No.	Samp	Samp Recov	Grour	Stand Test, I	Qu-tsf Comp	PP-tsf Pocke	Moistu Dry U	Rema
		3" Asphalt	0	.3				\square						
	12"	Crushed Stone	1 1	.3	-									
					-	1	SS	X		11	2.6	3.0	13.3	
					5 —	2	SS	X		10	1.4		11.6	
	Brown	Sandy Silty CLAY			- 	3	SS	X	⊻	8		1.3	10.8	
			12			4	SS	X	0	8		2.5	11.4	
	Gray S	Sandy Silty CLAY	13	5.0	- - - 15 — - - - -	5	SS	X		7		1.0	12.0	
		· ·	21	.0	20 -	6	SS	X		50/5"				
	End of	Boring at 21 feet												
Sample Typ SS - Driven Split Sp ST - Pressed Shelb CA - Continuous Flig RC - Rock Core CU - Cuttings CT - Continuous Tu	be_ boon y Tube ght Auger be		 O During Dri ⊈ At Comple	Brou Brou Illing etior	ndwat J n	er	12.0 fi 8.0 fi	<u>t.</u> <u>t.</u>	<u> </u>	H C D M	isa - H Fa - C C - D 1D - M	Boring Iollow S Continuc Driving C Iud Dril	Methoo Stem Aug ous Fligh Casing ling	gers the Augers



CLIENT TLF, In	с.						BOF		G #		B-0)4	
PROJECT NAME	Zionsville Hig	h School Locker Roon	n Additior				ALT	- & V	VITZIG	FILE #	241	N0394	
PROJECT LOCATIO	DN Zionsvil	le, IN											
	DRILLING and	SAMPLING INFORMATIO	N										
Date Started	7/25/24	Hammer Wt.	140lb	s.									
Date Completed	7/25/24	Hammer Drop	<u> </u>	•						TE	ST DA	ТА	
Boring Method	HSA	Spoon Sampler OD	<u>2</u> in	•									
Driller <u>C. Pet</u>	erman	Rig Type <u>_D-50 I ra(</u>					phics aphics		netration vs/foot	fined Strength	trometer	tent % ght (pcf)	
STRATA	SOIL CL	ASSIFICATION			e	le Type	ler Gra	d Wate	ard Per N - blov	Uncon	t Penel	re Con nit Wei	sks
ELEV.	SURFA	CE ELEVATION	Strata Depth	Depth Scale	Sampi No.	Sampl	Sampl Recov	Groun	Stand Test, N	Qu-tsf Compi	PP-tsf Pocke	Moistu Dry U	Rema
		TOPSOIL			_								
					-								
	Brown SAM	ND with Crushed Stone		-	1	ss	\square		41				
		(FILL)	4.0		-	-	Δ						
					1								
	Brown	and Gray Silty CLAV		5 -	2	SS	X		10		3.5	20.7	
	DIOWITZ	and Gray Silly CLAT	7.0		_								
			/.0	_	3	ss	∇		7	1.3		12.8	
-					_		Å						
					_								
_				10 -	4	SS	Χ		5		1.5	12.5	
						-	()						
_	Brown	Sandy Silty CLAY			-								
					-								
				15 -	- 5	ss	V		11		1.0	13.0	
-							Δ						
					-								
			18.0	-									
_													
	Gray	Sandy Silty CLAY		20 -	6	ss	∇		38		4.5	9.2	
_			21.0		_		Ň						
	End o	f Boring at 21 feet											
Sample Typ	be		Gro	undwa	ter					_	Boring	Method	_
S - Driven Split Sp T - Pressed Shelb	oon y Tube	0	During Drillin	ום מר		Dry f	<u>t.</u> 7		F C	ISA - H FA - C	lollow S Continue	Stem Auge ous Fliaht	ers Augers
A - Continuous Fli	ght Auger	- -	, a completi			Jyn	•		D	C - D	riving (Casing	0
U - Cuttings									IV	vi - ت		my	
I - Continuous Tu	be											Pad	e 1 of '



IENT TLF, In	C.						BOF	RINC	G #		B-0	5	
ROJECT NAME	Zionsville Hig	h School Locker Roor	n Addition				ALT	& V	VITZIG	FILE #	24IN	10394	
	DN Zionsvill	le, IN				_				_			
Date Started Date Completed	DRILLING and 7/25/24 7/25/24	SAMPLING INFORMATIO	N <u>140</u> Ibs <u>30</u> in.	S.						TE	ST DAT	ГА	
Boring Method	<u>пза</u> orman	Spoon Sampler OD D_50 Trac	∠_ın. ∼k ∧TV							_			
		Kig Type <u></u> _ Kig Type					hics phics		etration s/foot	ined Strengt	ometer	ent % ht (pcf)	
TRATA	SOIL CL	ASSIFICATION			e	e Type	er Grap ery Gra	d Water	ard Pen N - blow	Unconf ressive	t Penetr	re Conte nit Weig	rks
ELEV.	SURFA	CE ELEVATION	Strata Depth	Depth Scale	Sampl No.	Sampl	Sampl Recov	Groun	Standa Test, N	Qu-tsf Compi	PP-tsf Pocke	Moistu Dry U	Rema
		TOPSOIL	0.4	-	-								
					1	SS	X		4	1.4	2.0	13.7	
	Brown	Sandy Silty CLAY		5	2	SS	X		6	1.6		12.9	
				- - -	3	SS	X		6	1.7		13.2	
	E. J.		11.0	10 — -	4	SS	X		8	2.1	1.3	12.2	
		J											
<u>Sample Typ</u>		0	<u>Grou</u> During Drillin	undwate a	er	Drv fi	ł		н	SA - H	Boring	Method	rs

CA - Continuous Flight Auger RC - Rock Core CU - Cuttings CT - Continuous Tube

MATERIAL GRAPHICS LEGEND



ASPHALT: Asphalt



CL-ML: USCS Low Plasticity Silty Clay



FILL: Fill (made ground)

GRAVEL/COBBLES

SAMPLER SYMBOLS

SOIL PROPERTY SYMBOLS

N: Standard "N" penetration value. Blows per foot of a 140-lb hammer falling 30" on a 2" O.D. split-spoon. Qu: Unconfined Compressive Strength, tsf PP:Pocket Penetrometer, tsf LL: Liquid Limit, % PL: Plastic Limit, % PI: Plasticity Index, %

DRILLING AND SAMPLING SYMBOLS

GROUNDWATER SYMBOLS

Apparent water level noted while drilling.

 ∠ Apparent water level noted upon completion.

Apparent water level noted upon delayed time.

RELATIVE DENSITY & CONSISTANCY CLASSIFICATION (NON-COHESIVE SOILS)

<u>TERM</u>	<u>BLO</u>
Very Loose	
Loose	
Medium Dense	
Dense	
Very Dense	

WS PER FOOT 0 - 5 6 - 10 11 - 30 31 - 50 >51

SS: Split Spoon

RELATIVE DENSITY & CONSISTANCY CLASSIFICATION (COHESIVE SOILS)

<u>TERM</u>	<u>BLOWS PER FOOT</u>
Very Soft	0 - 3
Šoft	4 - 5
Medium Stiff	6 - 10
Stiff	11 - 15
Very Stiff	16 - 30
Hard	>31



Alt & Witzig

Telephone: Fax:

GENERAL NOTES

Project: Zionsville High School Locker Room Addition

Location: Zionsville, IN

Number: 24IN0394



APPENDIX **B**

Seismic Design Parameters Custom Soil Resource Report for Boone County, Indiana



OSHPD

24IN0394

Latitude, Longitude: 39.960303, -86.273066

Mulber Fields	e Waterf	Villiamsburg Ln Zionsville Community High School Trank Performing Arts Center American Legion Post 79 E 600 S Jennings Field
Date		7/29/2024, 10:57:19 AM
Design Cod	le Referenc	ce Document IBC-2015
Risk Catego	ory	
Туре	Value	Description MCE_ ground motion (for 0.2 second period)
S.	0.152	MCE_{R} ground motion. (for 1 0s period)
Suc	0.003	
S	0.243	
о _{М1}	0.2	
SDS	0.162	Numeric seismic design value at 0.2 second SA
S _{D1}	0.133	Numeric seismic design value at 1.0 second SA
Туре	Value	Description
SDC	С	Seismic design category
г _а	1.6	Site amplification factor at 0.2 second
Fv	2.4	Site amplification factor at 1.0 second
PGA	0.07	MCE _G peak ground acceleration
F _{PGA}	1.6	Site amplification factor at PGA
PGA _M	0.112	Site modified peak ground acceleration
ΤL	12	Long-period transition period in seconds
SsRT	0.152	Probabilistic risk-targeted ground motion. (0.2 second)
SsUH	0.167	Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration
SSD	1.5	Factored deterministic acceleration value. (0.2 second)
S1UH	0.096	Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration
S1D	0.6	Factored deterministic acceleration value. (1.0 second)
PGAd	0.6	Factored deterministic acceleration value. (Peak Ground Acceleration)

Туре	Value	Description
PGA _{UH}	0.07	Uniform-hazard (2% probability of exceedance in 50 years) Peak Ground Acceleration
C _{RS}	0.909	Mapped value of the risk coefficient at short periods
C _{R1}	0.864	Mapped value of the risk coefficient at a period of 1 s
C _V		Vertical coefficient

DISCLAIMER

While the information presented on this website is believed to be correct, <u>SEAOC</u> <u>(OSHPD</u> and its sponsors and contributors assume no responsibility or liability for its accuracy. The material presented in this web application should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. SEAOC / OSHPD do not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the seismic data provided by this website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site described by latitude/longitude location in the search results of this website.



United States Department of Agriculture

Natural Resources Conservation

Service

A product of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local participants

Custom Soil Resource Report for Boone County, Indiana

24IN0394



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (https://offices.sc.egov.usda.gov/locator/app?agency=nrcs) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/? cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	5
Soil Map	8
Soil Map	9
Legend	10
Map Unit Legend	. 11
Map Unit Descriptions	11
Boone County, Indiana	13
YctA—Crosby-Urban land-Treaty complex, fine-loamy subsoil, 0 to 2	
percent slopes	13
YmsB2—Miami silt loam-Urban land complex, 2 to 6 percent slopes,	
eroded	14
References	17

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.



MA	PLEGEND	MAP INFORMATION
Area of Interest (AOI) Area of Interest (AO) Spoil Area	The soil surveys that comprise your AOI were mapped at 1:12,000.
Soils Soil Map Unit Polygo Soil Map Unit Lines Soil Map Unit Points Special Point Features Blowout Borrow Pit Clay Spot Closed Depression	Image: Second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second second secon	Warning: Soil Map may not be valid at this scale. Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale. Please rely on the bar scale on each map sheet for map measurements. Source of Map: Natural Beasuress Concentration Service
Gravel Pit Gravelly Spot Landfill Lava Flow Marsh or swamp Mine or Quarry Miscellaneous Wate	US Routes Major Roads Local Roads Background Aerial Photography	Source of Map: Natural Resources Conservation Service Web Soil Survey URL: Coordinate System: Web Mercator (EPSG:3857) Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required. This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.
 Perennial Water Rock Outcrop Saline Spot Sandy Spot Severely Eroded Spot Sinkhole Slide or Slip Sodic Spot 	ot	Soil Survey Area: Boone County, Indiana Survey Area Data: Version 26, Sep 1, 2023 Soil map units are labeled (as space allows) for map scales 1:50,000 or larger. Date(s) aerial images were photographed: Jun 15, 2022—Jun 21, 2022 The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
YctA	Crosby-Urban land-Treaty complex, fine-loamy subsoil, 0 to 2 percent slopes	1.8	43.2%
YmsB2	Miami silt loam-Urban land complex, 2 to 6 percent slopes, eroded	2.3	56.8%
Totals for Area of Interest		4.1	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The

delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Boone County, Indiana

YctA—Crosby-Urban land-Treaty complex, fine-loamy subsoil, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: 2xf6n Elevation: 700 to 1,040 feet Mean annual precipitation: 37 to 46 inches Mean annual air temperature: 48 to 55 degrees F Frost-free period: 145 to 180 days Farmland classification: Not prime farmland

Map Unit Composition

Crosby and similar soils: 50 percent *Urban land:* 30 percent *Treaty, drained, and similar soils:* 20 percent *Estimates are based on observations, descriptions, and transects of the mapunit.*

Description of Crosby

Setting

Landform: Recessionial moraines, ground moraines, water-lain moraines Landform position (two-dimensional): Summit, backslope, footslope Landform position (three-dimensional): Rise Down-slope shape: Convex Across-slope shape: Linear Parent material: Silty material or loess over loamy till

Typical profile

Ap - 0 to 10 inches: silt loam Btg - 10 to 17 inches: silty clay loam 2Bt - 17 to 29 inches: clay loam 2BCt - 29 to 36 inches: loam 2Cd - 36 to 79 inches: loam

Properties and qualities

Slope: 0 to 2 percent
Depth to restrictive feature: 24 to 40 inches to densic material
Drainage class: Somewhat poorly drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Low to moderately high (0.01 to 0.20 in/hr)
Depth to water table: About 6 to 24 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 55 percent
Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water supply, 0 to 60 inches: Moderate (about 6.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified Land capability classification (nonirrigated): 2w Hydrologic Soil Group: C/D Ecological site: F111XA008IN - Wet Till Ridge Hydric soil rating: No

Description of Treaty, Drained

Setting

Landform: Swales, water-lain moraines, depressions Landform position (two-dimensional): Toeslope, footslope Landform position (three-dimensional): Dip Down-slope shape: Linear Across-slope shape: Concave Parent material: Silty material or loess over loamy till

Typical profile

Ap - 0 to 10 inches: silty clay loam A - 10 to 14 inches: silty clay loam Btg1 - 14 to 36 inches: silty clay loam 2Btg2 - 36 to 59 inches: loam 2C - 59 to 79 inches: loam

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Poorly drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: About 0 to 12 inches
Frequency of flooding: None
Frequency of ponding: Frequent
Calcium carbonate, maximum content: 40 percent
Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water supply, 0 to 60 inches: High (about 9.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified Land capability classification (nonirrigated): 2w Hydrologic Soil Group: B/D Ecological site: F111XA007IN - Till Depression Flatwood Hydric soil rating: Yes

YmsB2—Miami silt loam-Urban land complex, 2 to 6 percent slopes, eroded

Map Unit Setting

National map unit symbol: 2w586 Elevation: 180 to 1,040 feet Mean annual precipitation: 37 to 46 inches Mean annual air temperature: 48 to 55 degrees F Frost-free period: 145 to 180 days Farmland classification: Not prime farmland

Map Unit Composition

Miami, eroded, and similar soils: 50 percent *Urban land:* 35 percent *Minor components:* 15 percent *Estimates are based on observations, descriptions, and transects of the mapunit.*

Description of Miami, Eroded

Setting

Landform: Till plains Landform position (two-dimensional): Backslope, shoulder, footslope Landform position (three-dimensional): Side slope Down-slope shape: Convex Across-slope shape: Linear Parent material: Loess over loamy till

Typical profile

Ap - 0 to 8 inches: silt loam Bt - 8 to 13 inches: silty clay loam 2Bt - 13 to 31 inches: clay loam 2BCt - 31 to 36 inches: loam 2Cd - 36 to 79 inches: loam

Properties and qualities

Slope: 2 to 6 percent
Depth to restrictive feature: 24 to 40 inches to densic material
Drainage class: Moderately well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Low to moderately high (0.01 to 0.20 in/hr)
Depth to water table: About 24 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 45 percent
Maximum salinity: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Available water supply, 0 to 60 inches: Low (about 5.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified Land capability classification (nonirrigated): 2e Hydrologic Soil Group: C Ecological site: F111XA009IN - Till Ridge Other vegetative classification: Trees/Timber (Woody Vegetation) Hydric soil rating: No

Minor Components

Williamstown

Percent of map unit: 5 percent Landform: Till plains Landform position (two-dimensional): Backslope, shoulder Landform position (three-dimensional): Side slope Down-slope shape: Convex Across-slope shape: Linear Ecological site: F111XA009IN - Till Ridge Other vegetative classification: Trees/Timber (Woody Vegetation)

Hydric soil rating: No

Treaty

Percent of map unit: 5 percent Landform: Till plains Landform position (two-dimensional): Toeslope Landform position (three-dimensional): Dip Down-slope shape: Concave Across-slope shape: Concave Ecological site: F111XA007IN - Till Depression Flatwood Other vegetative classification: Mixed/Transitional (Mixed Native Vegetation) Hydric soil rating: Yes

Crosby

Percent of map unit: 5 percent Landform: Till plains Landform position (two-dimensional): Summit Landform position (three-dimensional): Interfluve Down-slope shape: Linear Across-slope shape: Convex Ecological site: F111XA008IN - Wet Till Ridge Other vegetative classification: Trees/Timber (Woody Vegetation) Hydric soil rating: No
References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/ nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2 053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/ home/?cid=nrcs142p2 053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. http://www.nrcs.usda.gov/wps/portal/nrcs/ detail/national/landuse/rangepasture/?cid=stelprdb1043084

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/ nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/? cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

Alt & Witzig Engineering, Inc.



4105 West 99th Street • Carmel, Indiana • 46032 Ph (317) 875-7000 • Fax (800) 875-6028

August 8, 2024

TLF, Inc. 3901 W. 86th St., Suite 200 Indianapolis, Indiana 46268 Attention: Ms. Tracy Chariton

> RE: Test-pit Investigation Zionsville High School Locker Room Existing Foundations Zionsville, Indiana Alt & Witzig Project: **24IN0418**

Dear Ms. Chariton:

Pursuant to our recent discussions we have performed observations of test pits excavated at the above referenced project site. The test pits were performed on July 25 and 26, 2024. A miniexcavator with an 18-inch bucket was used to excavate the test pits.

Excavations were performed at four (4) locations on the south side of the existing school, east of the natatorium. Locations were adjusted to avoid conflict with underground utilities. A Test Pit Location plan is provided as an attachment to this report.

The purpose of the excavation was to evaluate the size and depth of foundations at the test pit locations. The results of the investigation are presented on the following pages that include photos of the test pits and sketches showing the measured sizes and depths of the foundations.

Location TP-1



Foundation at Location TP-1



Foundation at TP-1



TP-1 Plan and Profile Dimensions



TP-2





TP-2

TP-2 Looking North



Zionsville High School Test Pits Alt & Witzig File: 24IN0418 Page 7



TP-3



TP-3 Looking West



Zionsville High School Test Pits Alt & Witzig File: 24IN0418 Page 9





TP-4 Looking Northwest

At the location of TP-4 the test pit was excavated to a depth of 61-inches. A foundation was not encountered in the test pit excavation. The test pit was terminated at this depth due to the location of the existing water line (shown by the blue flag on the left side of the picture above) and the limitations of the equipment.

The test pits were backfilled and areas of TP-1, 3, and 4 were seeded and covered with straw as shown below.



TP-1, 3, and 4 Restoration

Restoration of the area at TP-2 included backfilling the test pit and placing mulch as shown below.

Zionsville High School Test Pits Alt & Witzig File: 24IN0418 Page 11



Thank you for this opportunity to be of service. Feel free to contact us if you have any questions regarding this report.

Very truly yours,

ALT & WITZIG ENGINEERING, INC.

Nicholas Hayes, E.I.

Thomas J. Coffey, P.E.

APPENDIX

Test Pit Location Plan





PRE-BID REQUEST FOR INTERPRETATION/CLARIFICATION LOG	Response	hool Athletic Locker Room	Sheet S4-05 Will be added as part of addendum 1	Addressed in addendum 1	Addressed in addendum 1	Addressed in addendum 1	Addressed in addendum 1	Addressed in addendum 1	Future addendum
	Dwg./Spec.	High Scl							
	Request for Interpretation Item	224018.00 - Zionsville Community Renovations and Various Projects	Sheet S4-05 is missing from the documents. It's not noted in the sheet index, but it's called-out on structural (see S1-01). Please provide the missing sheet.	Please advise on the size of the building expansion joint (keynote 8 on A-11). Enlarged detail 8 on A5-03 does not provide any information.	The exterior wall detail on AP-01 shows 2-1/8" rigid insulation over Air Barrier. Details on A6-01 point to the masonry cavity insulation calling it " <i>Thermal and Air</i> <i>Barrier Assembly</i> ". There is no spec for insulation as air barrier system, but there is a " <i>Vapor-Permeable, Fluid-Applied Membrane Air Barrier</i> " spec section. It's our understanding that the detail on AP-01 is correct (separate insulation and air barrier products), but can you please confirm?	There are a few areas in the new building addition that do not have wall tags. Most of the rooms are shown on A4- 02 and A4-03, but areas at Vestibule and Office (such as A166 and A167) do not have tags. Please provide.	On sheet A3-11 section 1, there is a note regarding demo of existing counterflashing. Is removal of existing masonry required, or can the flashing be cut flush with the face of the brick, mortar joint grinded-out and tuck- pointed?	Is the existing brick, that will be visible to the new interior, required to be cleaned?	Is there a vertical reinforcement requirement for the interior walls that sit on thicken slab? Detail 5 on S3-03 does not indicate any, but detail 2 on S4-01 says "see plan", but nothing noted on the plans. Please note, almost all of the walls are partial height walls, extending 4" above ceiling.
	Date Received	ct No.	2/10/25	2/10/25	2/10/25	2/10/25	2/10/25	2/10/25	2/10/25
	RFI#	Proje(Additi	-	2	ю	4	വ	9	7