ADDENDUM
NO. 2

September 10, 2020

Zionsville Community Schools:
District Wide Mechanical Upgrades
Zionsville, IN 46077

TSC No. 219103.3

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications, and the Drawings dated August 5, 2005. Acknowledge receipt of the Addendum in the space provided on the Proposal Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 2-1 and Fanning/Howey Associates, Inc. Addendum No. 2, consisting of 9 items, 2 pages and Revised Drawing Sheets: Eagle Elementary Sheet M4.1.

A. SPECIFICATION SECTION - 01 21 00 –ALLOWANCES

1. Paragraph 3.01 CONTINGENCY ALLOWANCES

Change the following Allowance Amount:

A. Increase Allowance Bid Category No. 1 - Mechanical to $90,000

A D D E N D U M N O. 2

Zionsville HVAC Projects

Zionsville Community Schools
Zionsville, Indiana

Project Nos. 219127.03, 219129.01, 219130.01, 219131.02, 219134.00

Index of Contents

Addendum No. 2, 9 items, 2 pages
Revised Drawing Sheets: Eagle Elementary Sheet M4.1

Date: September 10, 2020

I hereby certify that this Addendum was prepared by me or under my direct supervision and that I am a duly registered Architect/Engineer under the Laws of the State of Indiana.

FANNING/HOWEY ASSOCIATES, INC.
ARCHITECTS/ENGINEERS/CONSULTANTS

Timothy C. Lehman, PE
Indiana Registration: 19800147
Expires: 7/31/2022

TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 2 to Drawings and Project Manual, dated August 5, 2020, for Zionsville HVAC Projects, for Zionsville Community Schools, 900 Mulberry Street, Zionsville, Indiana; as prepared by Fanning/Howey Associates, Inc., Indianapolis, Indiana.
This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

Each bidder shall acknowledge receipt of this Addendum in his proposal or bid.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum. (This includes miscellaneous items at the very end of this Addendum.)

RE: ALL BIDDERS

ITEM NO. 1. PROJECT MANUAL, 23 31 13 – METAL DUCTS

A. Article 3.9 – The intention of this article is not to clean the entire existing HVAC ductwork systems. The existing ductwork shall be cleaned as applicable to the work of this project and as noted on the drawings.

ITEM NO. 2. PROJECT MANUAL, 26 00 02 – ELECTRICAL SPECIFICATIONS

B. Part 2 – Add the following items.

"For the extension of existing branch circuits, follow information specified for extension of conductors. Label conductors per article 2.10."

"There is no expectation to pull new grounding conductors in existing circuits that are being reused."

"Attach color coding tape to existing conductors to identify phasing."

ITEM NO. 3. REVISED DRAWING SHEETS

A. Drawing Sheets: Eagle Elementary Sheet M4.1 has been revised, dated 9/10/20 and is included with and hereby made a part of this Addendum. These Drawings supersede the original documents.

ITEM NO. 4. DRAWING SHEET: PLEASANT VIEW SHEET M4.1

A. Key Note E2: Add the following to this note.

"The existing fire alarm system is a Honeywell XLS 3000 system."

ITEM NO. 5. DRAWING SHEET: PLEASANT VIEW SHEET M4.2

A. Key Note E2: Add the following to this note.

"The existing fire alarm system is a Honeywell XLS 3000 system."

ITEM NO. 6. DRAWING SHEET: FRESHMAN CENTER/ESC SHEET M2.2

A. Unit AHU-6: Delete all work associated with this unit from the project.

B. Key Note 2: Add the following to this note.

"The existing fire alarm system is a Honeywell XLS 3000 system."

C. Mechanical Plan Notes: Add note 3 as follows.

"Work related to relocating support wires from existing roof top units scheduled to be removed will be addressed by Cash Allowance.

ITEM NO. 7. DRAWING SHEET: FRESHMAN CENTER/ESC SHEET M2.3

A. Key Note 2: Add the following to this note.

"The existing fire alarm system is a Honeywell XLS 3000 system."

ITEM NO. 8. DRAWING SHEET: FRESHMAN CENTER/ESC SHEET M2.4

A. Key Note 2: Add the following to this note.

"The existing fire alarm system is a Honeywell XLS 3000 system."

ITEM NO. 9. DRAWING SHEET: FRESHMAN CENTER/ESC SHEET M4.1

A. Unit AHU-8: Delete all work associated with this unit from the project.

END OF ADDENDUM