

**ADDENDUM
NO. 01**

March 27, 2024

ZCS-Zionsville Community High School Soccer and Lacrosse Lighting
4400 S. 875 E.
Zionsville, IN, 46077

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications and the Drawings dated March 11, 2024, by Fanning Howey. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 1 - 1 through ADD 1 – 1 and attached Fanning/Howey Associates, Inc. Addendum No. 1 dated March 25, 2024 consisting of 2 pages.

A. Bid Category #01 – Sports Lighting Pre-Award Meeting with apparent low bidder is scheduled for April 4, 2024 at 9:00am local time (EST).

ADDENDUM NO. 1

Zionsville Community High School Soccer and Lacrosse Lighting

Project No. 223162.00

Zionsville Community Schools
Zionsville, Indiana

Index of Contents

Addendum No. 1, 3 items, 2 pages

Date: March 25, 2024

FANNING/HOWEY ASSOCIATES, INC.
ARCHITECTS/ENGINEERS/CONSULTANTS

TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 1 to Drawings and Project Manual, dated March 11, 2024 for Zionsville Community Schools, 900 Mulberry Street, Zionsville, Indiana; as prepared by Fanning/Howey Associates, Inc., Indianapolis, Indiana. This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

Each bidder shall acknowledge receipt of this Addendum in his proposal or bid.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum. (This includes miscellaneous items at the very end of this Addendum.)

RE: ALL BIDDERS

ITEM NO. 1. PROJECT MANUAL, SECTION 26 56 68 EXTERIOR ATHLETIC LIGHTING

A. Replace 2.2, D., as follows:

“D. Provide emergency lighting for bleachers. Provide one 67,000 lumen fixture mounted at 60 feet on each pole, aimed at bleachers for 1 footcandle average. Provide additional emergency lighting transfer components as required.”

B. Replace 2.4, C., as follows:

“C. Provide new emergency relay cabinet and contactors in existing location along with transfer accessories as required.”

C. Add 2.4, D., as follows:

“D. Provide new contactors for soccer pole lights in existing cabinet.”

D. Replace 3.2, A., 3., as follows:

“3. Playing and Other Designated Areas: Make field measurements at intersections of grids, dimensioned and located as specified in Part 1 “Performance Requirements” Article.”

E. Delete 3.2, A., 3., a., in its entirety.

ITEM NO. 2. DRAWING SHEET NO. E1.01

A. Delete general note 5., in its entirety.

B. Delete general note 6., in its entirety.

ITEM NO. 3. DRAWING SHEET NO. E2.01

A. Replace plan note L1 as follows:

"L1 PROVIDE NEW MUSCO PRECAST BASE AND SPORTS LIGHTING POLE. COORDINATE INSTALLATION SO AS NOT TO DAMAGE OR INTERFERE WITH THE OPERATION OF EXISTING SPORTS LIGHTING TO BE REMOVED. PROVIDE 2" CONDUIT AND WIRING TO MATCH EXISTING. SPLICE NEW CONDUCTORS TO EXISTING SPORTS LIGHTING CIRCUIT AT NEW ELECTRICAL HANDHOLE. CONNECT NEW EMERGENCY LIGHTING FIXTURES TO EMERGENCY CIRCUIT."

B. Replace plan note P1 as follows:

"P1 PROVIDE 24" X 36" FLUSH BOX AT THIS LOCATION FOR SITE EMERGENCY POWER. PROVIDE LID ENGRAVED WITH "EMERGENCY" LABEL."

C. Replace plan note P2 as follows:

"P2 INTERCEPT EXISTING CONDUIT AND WIRING SERVING SPORTS LIGHTING AND PROVIDE NEW ELECTRICAL HANDHOLE TO FACILITATE CONNECTION TO NEW SPORTS LIGHTING. REFERENCE BOX NOT SHOWN ON PLAN. EXISTING SPORTS LIGHTING SHALL REMAIN OPERATIONAL UNTIL NEW SPORTS LIGHTING HAS BEEN INSTALLED AND IS READY FOR FINAL CONNECTION. VERIFY EXACT LOCATION OF EXISTING CONDUIT AND WIRING IN FIELD."

D. Replace plan note P5 as follows:

"P5 PROVIDE (2 SETS OF 2 #8 AND #8 G) IN 2" CONDUIT FOR EMERGENCY BLEACHER LIGHTING."

END OF ADDENDUM